



The Commonwealth of Massachusetts

DEPARTMENT OF PUBLIC UTILITIES

PIPELINE ENGINEERING AND SAFETY DIVISION

INCIDENT REPORT

453 Worthington Street, Springfield, Massachusetts
November 23, 2012

PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington Street, Springfield, Massachusetts

November 23, 2012

Columbia Gas of Massachusetts

*Estimated Property Damage: \$1,310,000.00

Injuries: 17

Report Issued: September 19, 2014

* Estimated by Columbia Gas of Massachusetts

Table of Contents

I. INTRODUCTION	1
A. Scope of the Investigation	1
B. Overview of Incident	2
II. THE DEPARTMENT'S INVESTIGATION.....	3
A. Description of the Gas Facilities	3
B. Description of the Scene	3
C. Description of the Incident	4
1. CMA Inside Leak Investigation	4
2. Outside Leak Investigation	5
3. The Location of the Gas Service to 453 Worthington Street	6
4. Operator Actions After the Release of Gas	6
D. Pressure Test of the Gas Service Supplying 453 Worthington Street	8
III. ODORIZATION	10
IV. MAINTENANCE ACTIVITIES	10
V. LEAK SURVEYS.....	11
VI. FINDINGS AND CONCLUSIONS	12
A. Findings.....	12
1. Gas facilities on Worthington Street	12
2. The Incident.....	12
B. Conclusions	13
VII. OPERATOR CORRECTIVE ACTIONS	14

EXHIBITS

EXHIBIT LIST

- Exhibit 1:** CMA Incident Report to the U.S. Department of Transportation
- Exhibit 2:** CMA Telephonic Report to Department of Public Utilities
- Exhibit 3:** Sequence of Events:
3(a) CMA Review and Analysis of Incident
3(b) Timelines and Sequence of Events
3(c) Witness Statements
3(d) CMA Call Center Transcript
- Exhibit 4:** CMA Records of Gas Service Supplying 453 Worthington Street, Springfield
- Exhibit 5:** Photographs of Incident Area:
5(a) Aerial View of Incident Site
5(b) Ground View of Incident Site
5(c) The Damaged Gas Service Supplying 453 Worthington Street
In Situ
5(d) The Damaged Gas Service with Probe Bar
5(e) The Gas Service Connected to the Gas Main in Worthington Street
5(f) The Faded Yellow Line in Relation to the Damaged Gas Service
In Situ
5(g) Gas Service Regulator and Gas Meter
5(h) Gas Service Piping Inside 453 Worthington Street
- Exhibit 6:** Records of Cast Iron and Steel Main Underlying Worthington Street
- Exhibit 7:** CMA Facilities' Markout Completion Report - 454 Worthington Street, August 18, 2011
- Exhibit 8:** CMA Witness Statements
- Exhibit 9:** Drug and Alcohol Test Results (redacted)
- Exhibit 10:** CMA First Responder Record of Prior Damages to Facilities
- Exhibit 11:** Post Incident Odorant Test Results
- Exhibit 12:** Repairs at 453 Worthington Street, March 12, 2007
- Exhibit 13:** Leak Survey and Atmospheric Corrosion Inspection 453 Worthington Street
- Exhibit 14:** Leakage Survey Records - Worthington Street

Exhibit 15: Post Incident Leakage Survey Results

I. INTRODUCTION

A. Scope of the Investigation

The Massachusetts Department of Public Utilities (“Department”), Pipeline Engineering and Safety Division (“Division”), pursuant to G.L. c. 164, § 105A and a Federal Certification Agreement as provided for in 49 U.S.C. § 60105, has investigated a natural gas (“gas”) release at 453 Worthington Street, MA, on November 23, 2012 (“Incident”).¹ The release of gas contributed to an explosion, injuries of seventeen (17) persons, and an estimated \$ 1,310,000.00 in property damage as estimated by Columbia Gas of Massachusetts (“CMA” or “Operator”) (Exh. 1).

As part of the Department’s annual certification process by the United States Department of Transportation (“U.S. DOT”), the Department must report to the U.S. DOT

each accident or incident . . . involving a fatality, personal injury requiring hospitalization, or property damage or loss of more than an amount the Secretary establishes... and any other accident the [Department] considers significant, and a summary of the investigation by the [Department] of the cause and circumstances surrounding the accident or incident. 49 U.S.C. § 60105(c).

¹ Incident means any of the following events:

- (1) An event that involves a release of gas from a pipeline, or of liquefied natural gas, liquefied petroleum gas, refrigerant gas, or gas from an LNG facility, and that results in one or more of the following consequences:
 - (i) A death, or personal injury necessitating in-patient hospitalization;
 - (ii) Estimated property damage of \$50,000 or more, including loss to the operator and others, or both, but excluding cost of gas lost;
 - (iii) Unintentional estimated gas loss of three million cubic feet or more;
- (2) An event that results in an emergency shutdown of an LNG facility. Activation of an emergency shutdown system for reasons other than an actual emergency does not constitute an incident.
- (3) An event that is significant in the judgment of the operator, even though it did not meet the criteria of paragraphs (1) or (2) of this definition.

The purpose of this report is to inform the U.S. DOT as to the cause and circumstances surrounding the Incident.

The Department has established procedures for determining the nature and extent of violations of codes and regulations pertaining to the safety of pipeline facilities and the transportation of gas, including but not limited to, 220 C.M.R. §§ 101.00 through 113.00. See 220 C.M.R. § 69.00 et seq. The Division also enforces the U.S. DOT safety standards for gas pipeline systems as set forth in 49 C.F.R. Part 192 ("Part 192") and 49 C.F.R. Part 199 ("Part 199"). G.L. c. 164, § 105A.

B. Overview of Incident

At approximately 5:56 p.m. on November 23, 2012, the Department received notice from CMA of a release of gas at 453 Worthington Street, Springfield (Exh. 2). The caller reported that a CMA Utility Technician ("CMA Technician") punctured the gas service while investigating an odor complaint, resulting in the release of gas into the building that subsequently ignited and exploded (Exh. 3(a)). The Department dispatched two investigators to the scene. The damaged portion of the gas service was constructed of one and a quarter (1 ¼) inch plastic pipe that was inserted into a two (2) inch bare steel pipe, operating at approximately fifty three (53) pounds per square inch gage ("psig") (Exh. 4).²

² Pounds per square inch gauge refer to the pressure expressed in pounds exerted on one square inch of surface area. The designation "gauge," indicates the readings are already adjusted to ignore the surrounding atmospheric pressure, which is 14.7 psi at sea level. If psig gauge were not connected to any pressure source, it would read zero even though it is actually sensing 14.7 psi at sea level.

II. THE DEPARTMENT'S INVESTIGATION

A. Description of the Gas Facilities

Worthington Street, Springfield, is located in an area comprised of commercial properties and apartment buildings (Exh. 5(a)). The structure at 453 Worthington Street was a two-story building with a basement and a concrete foundation.

CMA operates two gas mains that underlie Worthington Street, a sixteen (16) inch coated steel gas main installed in 1980 and an eight (8) inch low pressure cast iron gas main installed in 1930 (Exh. 6).

The gas service to 453 Worthington Street was connected to the sixteen (16) inch coated steel gas main (Exh. 4). In 1993, the Operator renewed the gas service by inserting one and a quarter (1 ¼) inch plastic pipe into the original two (2) inch bare steel gas service supplying 453 Worthington Street (Exh. 4). CMA installed the gas service valve in the street at the gas main (Exhs. 4, 5(e)). Downstream of the gas service valve was a ninety (90) degree bend in the gas service, it then extended into 453 Worthington Street (Exhs. 4, 5(e)). The service regulator and gas meter were located inside the basement of the building (Exhs. 4, 5(g)). The operating pressure of the gas main at the time of the Incident was approximately fifty three (53) psig (Exh. 4).

B. Description of the Scene

On November 23, 2012, at approximately 8:20 p.m., Division investigators arrived at the scene of the Incident. Representatives from CMA, Springfield Fire and Police Departments, State Police, and the State Fire Marshal's Office were at the scene.

The building had been completely destroyed and debris from the explosion was blown onto Worthington Street, into adjacent properties, and several blocks away (Exhs. 5(a),(b)).

C. Description of the Incident

1. CMA Inside Leak Investigation

At 3:25 p.m., the CMA Call Center received a call from the property manager of 453 Worthington Street, reporting an odor of gas inside the building (Exh. 3(b),(d)). The property manager indicated to CMA that there was a slight odor of gas above the gas meters in the basement of 453 Worthington Street (Exh. 3(d)). CMA informed the property manager that someone would be onsite within an hour (Exh. 3(d)). There is no record that the CMA Call Center provided any further instructions to the caller (Exh. 3(d)).

At 3:29 p.m., CMA dispatched a CMA Technician to 453 Worthington Street (Exh. 3(b)). The CMA Technician arrived onsite at 3:49 p.m. (Exh. 3(b)). When the CMA Technician arrived, he parked in the adjacent lot and called the property manager to 453 Worthington Street (Exh. 3(c)).

When the manager arrived, they proceeded to the front of the building (Exh. 3(b)). At that time, the CMA Technician reported that he smelled a slight odor of gas (Exh. 3(a),(b),(c)).

The property manager took the CMA Technician into the basement of the building to the location of the gas service (Exh. 3(a),(b),(c)). The CMA Technician stated that he detected a slight odor of gas inside the building, but his combustible gas indicator ("CGI") machine did not record any gas readings (Exh. 3(a),(b),(c)). Using his CGI machine, the CMA Technician checked for gas around the meter, connections of the gas meter, gas service and associated gas

pipings (Exh. 3(a),(b),(c)). As he checked the gas service entrance inside the building, he noticed a soft clay material around the service entrance (Exh. 3(a),(b),(c)). However, his CGI machine detected no gas readings (Exh. 3(a),(b),(c)). There is no record that the CMA Technician checked any other utilities or appliances in the basement or checked any other areas inside the building (Exh. 3(a),(b),(c)). The CMA Technician then exited the building and commenced a leak investigation outside the building.

2. Outside Leak Investigation

CMA stated that the CMA Technician exited the building and located an electric manhole; he inserted the probe from his CGI machine into the manhole cover and obtained no gas readings. He then observed a faded yellow mark on the sidewalk that appeared to be in line with the gas service in the basement of 453 Worthington Street and the gas service valve in the street (Exhs. 3(a),(b),(c),5(f)). The CMA Technician went to his truck, and got a tool that punches a steel bar into the ground ("probe bar" or "bang bar") that creates a hole ("barhole") to probe for gas readings (Exhs. 3(a),(b),(c),5(d)).

The CMA Technician then placed a barhole in front of the building where the curb meets the sidewalk (Exh. 3(a),(b),(c)). The CMA Technician detected no gas readings with his CGI machine (Exh. 3(a),(b),(c)). The CMA Technician, using the faded yellow line as a reference, stepped off to the side of the yellow line and placed a second barhole at a seam on the concrete sidewalk against the foundation wall of 453 Worthington Street (Exhs. 3(a),(b),(c),5(c)). The CMA Technician could not go down very far before gas began to immediately escape (Exh. 3(a),(b),(c)). At 4:11 P.M., the CMA Technician called dispatch to inform them of this situation (Exh. 3(a),(b),(c)).

3. The Location of the Gas Service to 453 Worthington Street

CMA produced no records of any Dig Safe markout requests that it had received for 453 Worthington Street from January 1, 2007, to November 22, 2012. The most recent Dig Safe markout request received by CMA in the vicinity of 453 Worthington Street was for 454 Worthington Street on August 18, 2011 (Exh. 7). The scope of the 2011 excavation request was limited to the street and the sidewalk area in front of 454 Worthington Street (Exh. 7). CMA's records indicate that the markout technician reported that he marked two mains, and that no active records of a gas service was found for 454 Worthington Street (Exh. 7).

The service card for the gas service supplying 453 Worthington Street demonstrates, and photographs of the exposed gas service in situ confirm, that the gas service did not go in a straight line from the service tee connection at the sixteen (16) inch coated steel gas main and service shutoff valve to the building (Exhs. 4, 5(e)). Instead, the gas service ran on top of, and in line with, the gas main for approximately twenty two (22) inches from the service valve to where the plastic gas service turned ninety (90) degrees towards the building (Exhs. 4, 5(e)). The gas service records for 453 Worthington Street reveal that, in December, 1993, CMA renewed the gas service by inserting thirty (30) feet of one and a quarter (1 ¼) inch plastic pipe into the original two (2) inch gas steel service supplying 453 Worthington Street (Exh. 4).

4. Operator Actions after the Release of Gas

After puncturing the gas service with his probe bar, the CMA Technician evacuated 453 Worthington Street and returned to the basement to turn the valve on the gas service to the off position (Exhs. 3(a),(b),(c)). After shutting off the valve, the technician took CGI readings

at numerous manholes and made telephone calls to dispatch (Exh. 3(a),(b),(c)). There is no record that the CMA Technician or any other CMA employee checked any other buildings in the area for the presence of gas (Exh. 3(b),(c)).

At 4:14 p.m., CMA dispatched a distribution crew to the Incident site (Exh. 3(b)). CMA notified the fire department at 4:19 p.m. (Exh. 3(b)). At 4:23 p.m., CMA notified Western Massachusetts Electric Company ("WMECo") (Exh. 3(b)).

Upon the arrival of the distribution crew at 4:55 p.m. (Exh. 3(b)), CMA reported that the CMA Technician began to assist the street crew in blowing out debris in the curb box, the curb valve was shut off and he assisted in opening manholes in the area (Exh. 3(b),(c)).

The distribution crew located and cleared the service valve box to 453 Worthington Street (Exh. 8). The crew leader observed that the gas service to 453 Worthington Street came off the sixteen (16) inch coated steel gas main at a ninety (90) degree angle, and told a crew member to close the valve (Exhs. 4, 8). At approximately, 5:20 p.m., one hour and nine minutes after the CMA Technician informed CMA dispatch of the gas leak, the CMA distribution crew shut off the gas service valve (Exh. 3(b)).

CMA stated that the distribution crew checked the manholes and bar holes at the foundation wall with a CGI machine and acquired gas readings of ninety (90%) percent and fifty seven (57%) percent gas in air respectively (Exh. 8).

CMA reported that WMECo arrived onsite at 5:14 p.m. and spoke directly with Springfield Fire Department near the intersection of Worthington Street and Chestnut Street (Exhs. 3(b), 8).

After CMA shut off the gas service valve and the manhole covers had been removed, the gas reading in the manhole went to zero (0%) percent, and the fifty seven (57%) percent gas reading at the foundation wall decreased to fifty one (51%) percent (Exh. 8). After noting the drop in the readings the crew leader directed crew members to get behind the CMA truck, shortly after, the building at 453 Worthington Street exploded (Exh.8). At 5:27 p.m., CMA dispatch received a call from a distribution crew member reporting a gas explosion at 453 Worthington Street (Exh. 3(b)).

As a result of the explosion and subsequent fire, CMA reported that seventeen (17) people were injured (Exh. 1). CMA personnel present during the Incident were sent for Post Incident Drug and Alcohol Testing (Exh. 9). The CMA personnel underwent blood tests for drugs and alcohol (Exh.9). The blood test results showed that all CMA personnel tested negative for drugs and alcohol (Exh. 9).

D. Pressure Test of the Gas Service to Supplying 453 Worthington Street

Following their arrival at the Incident, the Department investigators requested that CMA pressure test the entire gas service from the connection at the sixteen (16) inch coated steel gas main to the service cock on the service riser located inside of 453 Worthington Street. CMA excavated at the gas main to expose the gas service tee, service valve, and the one and a quarter (1¼) inch plastic gas service piping as it entered the two (2) inch steel casing (Exhs. 4, 5(e)).

CMA first soap tested the short, approximately one (1) foot section of the gas service between the service tee and the service valve (Exh. 5(e)). The Department Investigators observed no indication of gas leakage at the service tee and service valve during the soap test.

CMA next isolated the service valve and service tee from the remaining portion of the gas service pipe supplying 453 Worthington Street.

On November 23, 2014, the day of the Incident, CMA stated that the operating pressure at its closest regulator station was 53 psig (Exh. 4). The Department investigators requested that CMA pressure test the remaining 29.5 feet of the gas service at 57 psig from the point of disconnect at the service valve in the street to the gas service cock located inside 453 Worthington Street (Exh. 5(h)).

The Department investigators observed a pressure loss and heard air blowing from the ground at a point close to the foundation wall. CMA excavated at the location of the blowing air, exposed the gas service in the sidewalk, and conducted another pressure test of the gas service at thirty (30) psig. The Department inspectors witnessed another pressure loss.

The source of the leak was determined to be an approximate half ($\frac{1}{2}$) inch puncture to the steel service casing which housed the one and a quarter ($1\frac{1}{4}$) inch plastic gas service pipe that was also punctured (Exh. 5(c),(d)). The circumference of the probe bar that the CMA technician used for the leak investigation was the same circumference as the half ($\frac{1}{2}$) inch hole in the casing and the plastic gas carrying pipe (Exhs. 1, 4, 5(d)).

The puncture in the gas service was approximately twenty one (21) inches to the right side of the faded yellow mark found on the sidewalk (Exhs. 3(a),(b),(c), 5(f)). The yellow mark was in line with the gas service valve that was located in the street, approximately twenty eight (28) feet away (Exhs. 4, 5(e),(f)).

CMA pressure tested the remaining (undamaged) portion of the plastic gas service pipe from the sidewalk to the service valve separation at the gas main, at a pressure of fifty six (56)

psig for fifteen (15) minutes. The Department investigators observed no pressure drop, indicating no leakage in that section of the plastic gas service pipe.

CMA responded that, the Technician who damaged the gas service supplying 453 Worthington Street had no history of damaging other CMA facilities during his employment over the last three years (Exh. 10). All qualification records for the CMA Technician were consistent with federal requirements.

III. ODORIZATION

The state regulation, 220 C.M.R. § 101.06(20), requires operators to odorize gas in their distribution systems. Gas must be “readily perceptible to the normal or average olfactory senses of a person coming from fresh uncontaminated air into a closed room containing [0.15 percent gas in air].” 220 C.M.R. § 101.06(20)(a). Operators are also required to conduct periodic sampling of odorant concentrations throughout their system. 220 C.M.R. § 101.06(20)(f). CMA conducts odorant sampling on a monthly basis.

On November 23, 2012, a qualified CMA employee conducted an odor level test in Springfield after the explosion (Exh. 11). The result of the test is as follows:

1. 352 Worthington Street, Springfield @ 6 p.m. - Odor level @ 0.03 percent gas in air.

The odor detectability level of gas in the air is within the limits prescribed by state regulation. See 220 C.M.R. § 101.06(20)(a).

IV. MAINTENANCE ACTIVITIES

A review of the CMA maintenance records for the eight (8) inch cast iron gas main, and sixteen (16) inch steel gas main underlying Worthington Street between Spring and Chestnut Street, and the one and a quarter (1 ¼) inch plastic gas service indicates CMA

performed maintenance work on these facilities on March 5, 2007; March 12, 2007; and March 17, 2008 (Exhs. 6, 12). On March 5, 2007, CMA reported a 0.30 percent gas reading at the foundation wall of 453 Worthington Street (Exh. 12). On March 12, 2007, CMA repaired an eight (8) inch joint leak on the cast iron gas main in front of 453 Worthington Street (Exh. 12).

On March 17, 2008, the customer at 453 Worthington reported a pulsating pressure regulator (Exh. 13). CMA installed a new regulator and reported no gas readings (Exh. 13).

CMA records indicate that on June 27, 2008, and August 23, 2012, CMA conducted an inspection of the inside gas piping at 453 Worthington Street (Exh. 13). CMA detected no leaks and reported that the pipe was in good condition (Exh. 13).

V. LEAK SURVEYS

In order to determine if other leak sources may have been contributing factors to the Incident, the Department reviewed the leak history of the eight (8) inch cast iron and sixteen (16) inch coated steel gas mains underlying Worthington Street between Spring and Chestnut Streets. Leakage surveys of gas mains and services are required by federal and state regulations. See 49 C.F.R. § 192.723(a) and 220 C.M.R. § 101.06(21).

On July 9, and 20, 2010, CMA performed a walking survey of the mains and services (Exh. 14). On February 23, 2012, CMA conducted a winter patrol survey that was limited to the eight (8) inch and sixteen (16) inch gas mains (Exh. 14). CMA conducted a mobile survey of the mains on April 18, 2012 (Exh. 14).

After the Incident, CMA conducted a leak survey of the surrounding area (Exh. 15). This survey detected gas readings that ranged from seventy four (74%) percent to fifty two (52%) percent in front of 453 and 454 Worthington Street (Exh. 15).

VI. FINDINGS AND CONCLUSIONS

A. Findings

1. Gas facilities on Worthington Street

- a. Worthington Street is located in a commercial district of Springfield, MA.
- b. An eight (8) inch low pressure cast iron gas main installed in 1930 and a sixteen (16) inch steel gas main installed in 1980 underlie the area in front of 453 Worthington Street.
- c. In 1993, CMA renewed the gas service supplying 453 Worthington Street by inserting one and a quarter (1¼) inch plastic pipe, into the original two (2) inch steel gas service.
- e. The gas service supplying 453 Worthington Street was connected to the sixteen (16) inch coated steel gas main.
- f. The operating pressure of the steel gas main and gas service at the time of the incident was approximately fifty three (53) psig.
- g. The gas service ran on top of, and in line with, the steel gas main for approximately twenty two (22) inches from the service valve to where the plastic gas service turned ninety (90) degrees towards 453 Worthington Street.

2. The Incident

- a. On November 23, 2013, at 3:25 p.m., the CMA Call Center received a call from the property manager reporting an odor of gas in the basement of 453 Worthington Street.
- b. At 3:49 p.m., CMA reported that its technician arrived on the scene. The CMA Technician stated that he smelled a slight odor of gas at the front of the building.
- c. The CMA Technician stated that he detected a slight odor of gas inside the basement of the building.
- d. Using his CGI machine, the CMA Technician checked for gas around the gas meter, connections of the gas meter, gas service, associated gas piping and detected no gas readings.
- e. The CMA technician checked the gas service entrance inside the building, but there is no record that the technician checked any other utilities or appliances inside the basement or checked any other areas inside the building.
- f. The CMA Technician conducted an outside leak investigation, and observed a faded yellow mark on the sidewalk that appeared to be in line with the gas

- service in the basement of 453 Worthington Street and the gas service valve in the street.
- g. The CMA Technician checked for gas readings in an electric manhole and then placed a barhole with his probe bar in front of the building where the curb meets the sidewalk and detected no gas readings at both locations.
 - h. The CMA Technician, using the faded yellow line as a reference, stepped off to the side of the yellow line and placed a second barhole at a seam on the concrete sidewalk against the foundation wall of 453 Worthington Street.
 - i. The CMA Technician punctured the gas service with his probe bar when he placed this barhole against the foundation wall. The Technician heard gas escaping immediately.
 - j. The CMA Technician evacuated the building and returned to the basement to turn the valve to the off position on the gas service.
 - k. At 4:11 p.m. the CMA Technician contacted CMA dispatch and informed them of the situation.
 - l. The fire department, CMA supervisor, and distribution crew arrived onsite to address the uncontrolled release of gas.
 - m. CMA detected gas readings of ninety (90%) percent and fifty seven (57%) percent in an electric manhole and at the foundation wall respectively.
 - n. At approximately 5:20 p.m. one hour and nine minutes after the Technician had punctured the gas service, the distribution crew shut off the gas supply to 453 Worthington by shutting off the gas service valve in the street.
 - o. After shutting the gas off, CMA reported that the gas reading in the manhole decreased to zero (0%) percent and the gas reading at the foundation wall had decreased to fifty one (51%) percent.
 - p. At 5:27 p.m. CMA employee's onsite reported to dispatch that the building at 453 Worthington Street had exploded.

B. Conclusions

The source of the release of gas at 453 Worthington Street, Springfield, was the damaged one and a quarter (1¼) inch gas service. The hole in the gas service was caused by an external force applied to the steel casing and plastic gas service, when the CMA Technician inserted a probe bar on the sidewalk, near the foundation wall outside of the building at 453 Worthington Street. The escaping gas entered and accumulated in the building and in the nearby manhole that contained the electric service connection to 453 Worthington Street. Due

to the elevated gas levels in the manhole which created an unsafe condition preventing entrance to shut off the electric service to the building was not shut off by WMECo.

After CMA shut off the supply of gas to the building, gas accumulated within the building and reached an explosive level. The accumulated gas ignited and the building exploded. Inside the building were many potential sources of ignition.

VII. OPERATOR CORRECTIVE ACTIONS

In the course of its investigation into the cause and circumstances of this Incident, the Department concluded two enforcement actions. In Bay State Gas Company d/b/a Columbia Gas of Massachusetts, D.P.U 12-PL-11, the Department investigated CMA's actions specifically related to the release of gas that resulted in the Incident. The other enforcement action in Bay State Gas Company d/b/a Columbia Gas of Massachusetts, D.P.U 12-PL-12, concerned CMA's field activities with respect to CMA's operating and maintenance activities in the Springfield Division after the Incident.


CMA agreed to perform a number of actions with the intent of minimizing the possibility of a recurrence of this Incident. CMA will review and revise its Operating & Maintenance ("O&M") manual procedures concerning the utilization of probe bar tools for locating leaks. This review includes, but is not limited to: (a) the use of current tools CMA uses for leakage pinpointing; (b) employee (and contract employee) training on probe bar safety (i.e., depth of insertion, checking point (sharpness) of probe bars, locating facilities prior to bar-holing); (c) training on when and how to use a probe bar when performing a leak investigation; (d) processes allowing technicians immediate on-site access to service cards.

CMA will review, and modify as appropriate, the effectiveness of its: O&M procedures; emergency response procedures; training program(s) for call center representatives; operator qualification (and requalification) methods, training procedures and processes. CMA will also evaluate its current drug and alcohol testing facilities, including after hours facilities, to ensure that CMA has the necessary coverage to meet federal mandated testing time guidelines.

CMA stated that it will be abandoning 200 feet of cast iron gas main on Fairbank Place, 1,000 feet of eight (8) inch cast iron gas main, and 100 feet of twelve (12) inch cast iron gas main on Worthington Street. In addition, CMA will install 200 feet of two (2) inch plastic on Fairbank Place (60 psig) and 400 feet of two (2) inch plastic pipe on Worthington Street (60 psig).

EXHIBIT 1

CMA Incident Report to the U.S. Department of Transportation

NOTICE: This report is required by 49 CFR Part 191. Failure to report can result in a civil penalty not to exceed 100,000 for each violation for each day that such violation persists except that the maximum civil penalty shall not exceed \$1,000,000 as provided in 49 USC 60122.		OMB NO: 2137-0522 EXPIRATION DATE: 01/31/2014	
 U.S. Department of Transportation Pipeline and Hazardous Materials Safety Administration	Report Date:	12/02/2012	
	No.	20120098- 15555	
	(DOT Use Only)		
INCIDENT REPORT - GAS DISTRIBUTION SYSTEM			
A federal agency may not conduct or sponsor, and a person is not required to respond to, nor shall a person be subject to a penalty for failure to comply with a collection of information subject to the requirements of the Paperwork Reduction Act unless that collection of information displays a current valid OMB Control Number. The OMB Control Number for this information collection is 2137-0522. Public reporting for this collection of information is estimated to be approximately 10 hours per response, including the time for reviewing instructions, gathering the data needed, and completing and reviewing the collection of information. All responses to this collection of information are mandatory. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden to: Information Collection Clearance Officer, PHMSA, Office of Pipeline Safety (PHP-30) 1200 New Jersey Avenue, SE, Washington, D.C. 20590.			
INSTRUCTIONS <i>Important: Please read the separate instructions for completing this form before you begin. They clarify the information requested and provide specific examples. If you do not have a copy of the instructions, you can obtain one from the PHMSA Pipeline Safety Community Web Page at http://www.phmsa.dot.gov/pipeline.</i>			
PART A - KEY REPORT INFORMATION			
Report Type: (select all that apply)		Original:	Supplemental:
		Yes	Final:
Last Revision Date			
1. Operator's OPS-issued Operator Identification Number (OPID):		1209	
2. Name of Operator		COLUMBIA GAS OF MASSACHUSETTS	
3. Address of Operator:			
3a. Street Address		4 TECHNOLOGY DRIVE	
3b. City		WESTBOROUGH	
3c. State		Massachusetts	
3d. Zip Code		01581	
4. Local time (24-hr clock) and date of the Incident:		11/23/2012 17:25	
5. Location of Incident:			
5a. Street Address or location description		453 Worthington Street	
5b. City		Springfield	
5c. County or Parish		Hampden	
5d. State:		Massachusetts	
5e. Zip Code:		01105	
5f. Latitude:		42.10668	
Longitude:		-72.589386	
6. National Response Center Report Number:		1031399	
7. Local time (24-hr clock) and date of initial telephonic report to the National Response Center:		11/23/2012 18:23	
8. Incident resulted from:		Unintentional release of gas	
9. Gas released:		Natural Gas	
- Other Gas Released Name:			
10. Estimated volume of gas released - Thousand Cubic Feet (MCF):		26.00	
11. Were there fatalities?		No	
- If Yes, specify the number in each category:			
11a. Operator employees			
11b. Contractor employees working for the Operator			
11c. Non-Operator emergency responders			
11d. Workers working on the right-of-way, but NOT associated with this Operator			
11e. General public			
11f. Total fatalities (sum of above)			
12. Were there injuries requiring inpatient hospitalization?		Yes	
- If Yes, specify the number in each category:			
12a. Operator employees		2	
12b. Contractor employees working for the Operator		0	
12c. Non-Operator emergency responders		12	
12d. Workers working on the right-of-way, but NOT associated with this Operator		1	
12e. General public		2	
12f. Total injuries (sum of above)		17	
13. Was the pipeline/facility shut down due to the incident?		No	
- If No, Explain:		Service to building was shut-off due to incident	

- If Yes, complete Questions 13a and 13b: (use local time, 24-hr clock)	
13a. Local time and date of shutdown:	
13b. Local time pipeline/facility restarted:	
- Still shut down? (* Supplemental Report Required)	
14. Did the gas ignite?	Yes
15. Did the gas explode?	Yes
16. Number of general public evacuated:	20
17. Time sequence (use local time, 24-hour clock):	
17a. Local time operator identified Incident:	11/23/2012 17:30
17b. Local time operator resources arrived on site:	11/23/2012 17:30
PART B - ADDITIONAL LOCATION INFORMATION	
1. Was the Incident on Federal land?	No
2. Location of Incident	Private property
3. Area of Incident:	Transition Area
	Specify: Wall sleeve
	If Other, Describe:
	Depth of Cover:
4. Did Incident occur in a crossing?	No
- If Yes, specify type below:	
- If Bridge crossing –	
Cased/ Uncased:	
- If Railroad crossing –	
Cased/ Uncased/ Bored/drilled	
- If Road crossing –	
Cased/ Uncased/ Bored/drilled	
- If Water crossing –	
Cased/ Uncased	
Name of body of water (If commonly known):	
Approx. water depth (ft):	
PART C - ADDITIONAL FACILITY INFORMATION	
1. Indicate the type of pipeline system:	Natural Gas Distribution, privately owned
	- If Other, specify:
2. Part of system involved in Incident:	Service
	- If Other, specify:
2a. Year "Part of system involved in Incident" was installed:	1993
	Unknown?
3. When "Main" or "Service" is selected as the "Part of system involved in Incident" (from PART C, Question 2), provide the following:	
3a. Nominal diameter of pipe (in):	1.25
3b. Pipe specification (e.g., API 5L, ASTM D2513):	ASTM 02513
	Unknown?
3c. Pipe manufacturer:	Phillips or Plexco
	Unknown?
3d. Year of manufacture:	Yes
	Unknown?
4. Material involved in Incident:	Plastic
	- If Other, specify:
4a. If Steel, Specify seam type:	
	None/Unknown?
4b. If Steel, Specify wall thickness (inches):	
	Unknown?
4c. If Plastic, Specify type:	Polyethylene (PE)
	- If Other, describe:
4d. If Plastic, Specify Standard Dimension Ratio (SDR):	
	Or wall thickness: .121
	Unknown?
4e. If Polyethylene (PE) is selected as the type of plastic in Part C, Question 4.c:	
- Specify PE Pipe Material Designation Code (i.e. 2406, 3408, etc.)	3408
	Unknown?
5. Type of release involved :	Mechanical Puncture
- If Mechanical Puncture - Specify Approx size:	
Approx. size: in. (axial):	.50
in. (circumferential):	.50
- If Leak - Select Type:	
	- If Other, Describe:

- If Rupture - Select Orientation:	
- If Other, Describe:	
Approx. size: (widest opening):	
(length circumferentially or axially):	
- If Other - Describe:	

PART D - ADDITIONAL CONSEQUENCE INFORMATION

1. Class Location of Incident :	Class 2 Location
2. Estimated Property Damage :	
2a. Estimated cost of public and non-Operator private property damage	\$ 1,000,000
2b. Estimated cost of Operator's property damage & repairs	\$ 100,000
2c. Estimated cost of Operator's emergency response	\$ 10,000
2d. Estimated other costs	\$ 200,000
- Describe:	residual structure glass damage
2e. Total estimated property damage (sum of above)	\$ 1,310,000

Cost of Gas Released

2f. Estimated cost of gas released	\$ 300
3. Estimated number of customers out of service:	
3a. Commercial entities	1
3b. Industrial entities	0
3c. Residences	0

PART E - ADDITIONAL OPERATING INFORMATION

1. Estimated pressure at the point and time of the Incident (psig):	57.00
2. Normal operating pressure at the point and time of the Incident (psig):	57.00
3. Maximum Allowable Operating Pressure (MAOP) at the point and time of the Incident (psig):	60.00
4. Describe the pressure on the system relating to the Incident:	Pressure did not exceed MAOP
5. Was a Supervisory Control and Data Acquisition (SCADA) based system in place on the pipeline or facility involved in the Incident?	No
- If Yes:	
5a. Was it operating at the time of the Incident?	
5b. Was it fully functional at the time of the Incident?	
5c. Did SCADA-based information (such as alarm(s), alert(s), event(s), and/or volume or pack calculations) assist with the detection of the Incident?	
5d. Did SCADA-based information (such as alarm(s), alert(s), event(s), and/or volume calculations) assist with the confirmation of the Incident?	
6. How was the Incident initially identified for the Operator?	Local Operating Personnel, including contractors
6a. If "Controller", "Local Operating Personnel, including contractors", "Air Patrol", or "Ground Patrol by Operator or its contractor" is selected in Question 6, specify the following:	Operator employee
- If Other, Specify:	
7. Was an investigation initiated into whether or not the controller(s) or control room issues were the cause of or a contributing factor to the Incident?	No, the Operator did not find that an investigation of the controller(s) actions or control room issues was necessary due to: (provide an explanation for why the Operator did not investigate)
- If No, the operator did not find that an investigation of the controller(s) actions or control room issues was necessary due to: (provide an explanation for why the operator did not investigate)	Incident was human error and isolated to damage on service
- If Yes, Specify investigation result(s) (select all that apply):	
- Investigation reviewed work schedule rotations, continuous hours of service (while working for the Operator), and other factors associated with fatigue	
- Investigation did NOT review work schedule rotations, continuous hours of service (while working for the Operator), and other factors associated with fatigue	
- Provide an explanation for why not:	
- Investigation identified no control room issues	
- Investigation identified no controller issues	
- Investigation identified incorrect controller action or controller error	
- Investigation identified that fatigue may have affected the controller(s) involved or impacted the involved controller(s) response	
- Investigation identified incorrect procedures	
- Investigation identified incorrect control room equipment operation	

- Investigation identified maintenance activities that affected control room operations, procedures, and/or controller response	
- Investigation identified areas other than those above	
Describe:	
PART F - DRUG & ALCOHOL TESTING INFORMATION	
1. As a result of this Incident, were any Operator employees tested under the post-accident drug and alcohol testing requirements of DOT's Drug & Alcohol Testing regulations?	Yes
- If Yes:	
1a. Specify how many were tested:	6
1b. Specify how many failed:	0
2. As a result of this Incident, were any Operator contractor employees tested under the post-accident drug and alcohol testing requirements of DOT's Drug & Alcohol Testing regulations?	No
- If Yes:	
2a. Specify how many were tested:	
2b. Specify how many failed:	
PART G - CAUSE INFORMATION	
Select only one box from PART G in shaded column on left representing the Apparent Cause of the Incident, and answer the questions on the right. Describe secondary, contributing, or root causes of the Incident in the narrative (PART H).	
Apparent Cause:	G8 - Other Incident Cause
G1 - Corrosion Failure – only one sub-cause can be picked from shaded left-hand column	
Corrosion Failure Sub-Cause:	
- If External Corrosion:	
1. Results of visual examination:	
- If Other, Specify:	
2. Type of corrosion:	
- Galvanic	
- Atmospheric	
- Stray Current	
- Microbiological	
- Selective Seam	
- Other	
- If Other, Describe:	
3. The type(s) of corrosion selected in Question 2 is based on the following:	
- Field examination	
- Determined by metallurgical analysis	
- Other	
- If Other, Describe:	
4. Was the failed item buried under the ground?	
- If Yes:	
4a. Was failed item considered to be under cathodic protection at the time of the incident?	
- If Yes, Year protection started:	
4b. Was shielding, tenting, or disbonding of coating evident at the point of the incident?	
4c. Has one or more Cathodic Protection Survey been conducted at the point of the incident?	
If "Yes, CP Annual Survey" – Most recent year conducted:	
If "Yes, Close Interval Survey" – Most recent year conducted:	
If "Yes, Other CP Survey" – Most recent year conducted:	
- If No:	
4d. Was the failed item externally coated or painted?	
5. Was there observable damage to the coating or paint in the vicinity of the corrosion?	
6. Pipeline coating type, if steel pipe is involved:	
- If Other, Describe:	
- If Internal Corrosion:	
7. Results of visual examination:	
- If Other, Describe:	
8. Cause of corrosion (select all that apply):	
- Corrosive Commodity	

- Water drop-out/Acid	
- Microbiological	
- Erosion	
- Other	
- If Other, Specify:	
9. The cause(s) of corrosion selected in Question 8 is based on the following: <i>(select all that apply)</i> :	
- Field examination	
- Determined by metallurgical analysis	
- Other	
- If Other, Describe:	
10. Location of corrosion <i>(select all that apply)</i> :	
- Low point in pipe	
- Elbow	
- Drop-out	
- Other	
- If Other, Describe:	
11. Was the gas/fluid treated with corrosion inhibitor or biocides?	
12. Were any liquids found in the distribution system where the Incident occurred?	
Complete the following if any Corrosion Failure sub-cause is selected AND the "Part of system involved in Incident" (from PART C, Question 2) is Main, Service, or Service Riser.	
13. Date of the most recent Leak Survey conducted	
14. Has one or more pressure test been conducted since original construction at the point of the Incident?	
- If Yes:	
Most recent year tested:	
Test pressure:	
G2 – Natural Force Damage – only one sub-cause can be picked from shaded left-handed column	
Natural Force Damage – Sub-Cause:	
- If Earth Movement, NOT due to Heavy Rains/Floods:	
1. Specify:	
- If Other, Specify:	
- If Heavy Rains/Floods:	
2. Specify:	
- If Other, Specify:	
- If Lightning:	
3. Specify:	
- If Temperature:	
4. Specify:	
- If Other, Specify:	
- If High Winds:	
- Other Natural Force Damage:	
5. Describe:	
Complete the following if any Natural Force Damage sub-cause is selected.	
6. Were the natural forces causing the Incident generated in conjunction with an extreme weather event?	
6.a If Yes, specify <i>(select all that apply)</i> :	
- Hurricane	
- Tropical Storm	
- Tornado	
- Other	
- If Other, Specify:	
G3 – Excavation Damage – only one sub-cause can be picked from shaded left-hand column	
Excavation Damage – Sub-Cause:	
- If Excavation Damage by Operator (First Party):	
- If Excavation Damage by Operator's Contractor (Second Party):	
- If Excavation Damage by Third Party:	
- If Previous Damage due to Excavation Activity:	

Complete the following ONLY IF the "Part of system involved in Incident" (from Part C, Question 2) is Main, Service, or Service Riser.	
1. Date of the most recent Leak Survey conducted	
2. Has one or more pressure test been conducted since original construction at the point of the Incident?	
- If Yes:	
Most recent year tested:	
Test pressure:	
Complete the following if Excavation Damage by Third Party is selected.	
3. Did the operator get prior notification of the excavation activity?	
3a. If Yes, Notification received from: (select all that apply):	
- One-Call System	
- Excavator	
- Contractor	
- Landowner	
Complete the following mandatory CGA-DIRT Program questions if any Excavation Damage sub-cause is selected.	
4. Do you want PHMSA to upload the following information to CGA-DIRT (www.cga-dirt.com)?	
5. Right-of-Way where event occurred (select all that apply):	
- Public	
- If Public, Specify:	
- Private	
- If Private, Specify:	
- Pipeline Property/Easement	
- Power/Transmission Line	
- Railroad	
- Dedicated Public Utility Easement	
- Federal Land	
- Data not collected	
- Unknown/Other	
6. Type of excavator :	
7. Type of excavation equipment :	
8. Type of work performed :	
9. Was the One-Call Center notified?	
9a. If Yes, specify ticket number:	
9b. If this is a State where more than a single One-Call Center exists, list the name of the One-Call Center notified:	
10. Type of Locator:	
11. Were facility locate marks visible in the area of excavation?	
12. Were facilities marked correctly?	
13. Did the damage cause an interruption in service?	
13a. If Yes, specify duration of the interruption:	
14. Description of the CGA-DIRT Root Cause (select only the one predominant first level CGA-DIRT Root Cause and then, where available as a choice, the one predominant second level CGA-DIRT Root Cause as well):	
- Root Cause Description:	
- If One-Call Notification Practices Not Sufficient, specify:	
- If Locating Practices Not Sufficient, specify:	
- If Excavation Practices Not Sufficient, specify:	
- If Other/None of the Above (explain), specify:	
G4 - Other Outside Force Damage - only one sub-cause can be selected from the shaded left-hand column	
Other Outside Force Damage – Sub-Cause:	
- If Nearby Industrial, Man-made, or Other Fire/Explosion as Primary Cause of Incident:	
- If Damage by Car, Truck, or Other Motorized Vehicle/Equipment NOT Engaged in Excavation:	
1. Vehicle/Equipment operated by:	
- If Damage by Boats, Barges, Drilling Rigs, or Other Maritime Equipment or Vessels Set Adrift or Which Have Otherwise Lost Their Mooring:	
2. Select one or more of the following IF an extreme weather event was a factor:	
- Hurricane	
- Tropical Storm	
- Tornado	
- Heavy Rains/Flood	

- Other		Page 7 of 10
- If Other, Specify:		
- If Routine or Normal Fishing or Other Maritime Activity NOT Engaged in Excavation:		
- If Electrical Arcing from Other Equipment or Facility:		
- If Previous Mechanical Damage NOT Related to Excavation:		
<i>Complete the following ONLY IF the "Part of system involved in Incident" (from Part C, Question 2) is Main, Service, or Service Riser.</i>		
3. Date of the most recent Leak Survey conducted:		
4. Has one or more pressure test been conducted since original construction at the point of the Incident?		
- If Yes:		
Most recent year tested:		
Test pressure (psig):		
- If Intentional Damage:		
5. Specify:		
- If Other, Specify:		
- If Other Outside Force Damage:		
6. Describe:		
G5 - Pipe, Weld, or Joint Failure - only one sub-cause can be selected from the shaded left-hand column		
Pipe, Weld or Joint Failure – Sub-Cause:		
- If Body of Pipe:		
1. Specify:		
- If Other, Describe:		
- If Butt Weld:		
2. Specify:		
- If Other, Describe:		
- If Fillet Weld:		
3. Specify:		
- If Other, Describe:		
- If Pipe Seam:		
4. Specify:		
- If Other, Describe:		
- If Threaded Metallic Pipe:		
- If Mechanical Fitting:		
5. Specify the mechanical fitting involved:		
- If Other, Describe:		
6. Specify the type of mechanical fitting:		
- If Other, Describe:		
7. Manufacturer:		
8. Year manufactured:		
9. Year installed:		
10. Other attributes:		
11. Specify the two materials being joined:		
11a. First material being joined:		
- Steel		
- Cast/Wrought Iron		
- Ductile Iron		
- Copper		
- Plastic		
- Unknown		
- Other		
- If Other, Specify:		
11b. If Plastic, specify:		
- If Other Plastic, specify:		
11c. Second material being joined:		
- Steel		
- Cast/Wrought Iron		
- Ductile Iron		
- Copper		
- Plastic		

- Unknown	
- Other	
- If Other, Specify:	
11d. If Plastic, specify:	
- If Other Plastic, Specify:	
12. If used on plastic pipe, did the fitting – as designed by the manufacturer – include restraint?	
12a. If Yes, specify:	
- If Compression Fitting:	
13. Fitting type:	
14. Manufacturer:	
15. Year manufactured:	
16. Year installed:	
17. Other attributes:	
18. Specify the two materials being joined:	
18a. First material being joined:	
- Steel	
- Cast/Wrought Iron	
- Ductile Iron	
- Copper	
- Plastic	
- Unknown	
- Other	
- If Other, specify:	
18b. If Plastic, specify:	
- If Other Plastic, specify:	
18c. Second material being joined:	
- Steel	
- Cast/Wrought Iron	
- Ductile Iron	
- Copper	
- Plastic	
- Unknown	
- Other	
If Other, specify:	
18d. If Plastic, specify:	
- Other Plastic, specify:	
- If Fusion Joint:	
19. Specify:	
- If Other, Specify:	
20. Year installed:	
21. Other attributes:	
22. Specify the two materials being joined:	
22a. First material being joined:	
- If Other, Specify:	
22b. Second material being joined:	
- If Other, Specify:	
- If Other Pipe, Weld, or Joint Failure:	
23. Describe:	
Complete the following if any Pipe, Weld, or Joint Failure sub-cause is selected.	
24. Additional Factors (select all that apply):	
- Dent	
- Gouge	
- Pipe Bend	
- Arc Burn	
- Crack	
- Lack of Fusion	
- Lamination	
- Buckle	
- Wrinkle	
- Misalignment	
- Burnt Steel	
- Other	
25. Was the Incident a result of:	
- Construction defect	
Specify:	
- Material defect	

Specify:	
- If Other, Specify:	
- Design defect	
- Previous damage	
26. Has one or more pressure test been conducted since original construction at the point of the Incident?	
- If Yes:	
Most recent year tested:	
Test pressure:	
G6 - Equipment Failure - only one sub-cause can be selected from the shaded left-hand column	
Equipment Failure – Sub-Cause:	
- If Malfunction of Control/Relief Equipment:	
1. Specify:	
- Control Valve	
- Instrumentation	
- SCADA	
- Communications	
- Block Valve	
- Check Valve	
- Relief Valve	
- Power Failure	
- Stopple/Control Fitting	
- Pressure Regulator	
- Other	
- If Other, Specify:	
- If Threaded Connection Failure:	
2. Specify:	
- If Other, Specify:	
- If Non-threaded Connection Failure:	
3. Specify:	
- If Other, Specify:	
- If Valve:	
4. Specify:	
- If Other, Specify:	
4a. Valve type:	
4b. Manufactured by:	
4c. Year manufactured:	
- If Other Equipment Failure:	
5. Describe:	
G7 - Incorrect Operation - only one sub-cause can be selected from the shaded left-hand column	
Incorrect Operation Sub-Cause:	
- If Damage by Operator or Operator's Contractor NOT Related to Excavation and NOT due to Motorized Vehicle/Equipment Damage:	
- If Valve Left or Placed in Wrong Position, but NOT Resulting in an Overpressure:	
- If Pipeline or Equipment Overpressured:	
- If Equipment Not Installed Properly:	
- If Wrong Equipment Specified or Installed:	
- If "Other Incorrect Operation:	
1. Describe:	
Complete the following if any Incorrect Operation sub-cause is selected.	
2. Was this Incident related to: (select all that apply)	
- Inadequate procedure	
- No procedure established	
- Failure to follow procedure	
- Other	
- If Other, Describe:	
3. What category type was the activity that caused the Incident:	
4. Was the task(s) that led to the Incident identified as a covered task in your	

Operator Qualification Program?		Page 10 of 10
4a. If Yes, were the individuals performing the task(s) qualified for the task(s)?		
G8 - Other Incident Cause - only one sub-cause can be selected from the shaded left-hand column		
Other Incident Cause – Sub-Cause:		Miscellaneous
- If Miscellaneous:		
1. Describe:		Operator employee punctured service line with probe bar while investigating odor call.
- If Unknown:		
2. Specify:		
PART H - NARRATIVE DESCRIPTION OF THE INCIDENT		
Operator employee responded to odor call in basement of 453 Worthington St. After obtaining zero levels inside of building, employee began investigation outside. using probe bar employee struck and punctured service line causing gas to enter building. Released gas ultimately ignited, causing explosion.		
File Full Name Note: The users have to sign in to view the attachment if there is no current user session.		
PART I - PREPARER AND AUTHORIZED SIGNATURE		
Preparer's Name		Brian P Normoyle
Preparer's Title		Operations Compliance Manager
Preparer's Telephone Number		508-836-7301
Preparer's E-mail Address		bnormoyle@nisource.com
Preparer's Facsimile Number		508-836-7070
Authorized Signature		
Authorize Signature's Name		Brian P Normoyle
Authorized Signature's Title		Operations Compliance Manager
Authorized Signature Telephone Number		508-836-7301
Authorized Signature's Email Address		bnormoyle@nisource.com
Date		12/02/2012

EXHIBIT 2

CMA Telephonic Report to Department of Public Utilities

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
FIRST SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: December 10, 2012

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-1-4: Refer to the Operator's Emergency Plan, Section 4.10. Provide the notification time, notification number (the Operator called to the DPU), reporting personnel name, and incident details CMA provided to the Massachusetts Department of Public Utilities on November 23, 2012. Include in your response, a copy of the preliminary report, Form C 1540.

Response: CMA Logistics coordinator Patricia Kurey placed a telephone call to the DPU at 17:56 on November 23, 2012. Ms. Kurey left a voice message because that telephone was not answered. The Company is currently reviewing phone records to identify the number called and will supplement this response upon confirmation of that number.

A Form C 1540 was not completed for this incident.

EXHIBIT 3

Sequence of Events:

- 3(a) CMA Review and Analysis of Incident
- 3(b) Timelines and Sequence of Events
- 3(c) Witness Statements
- 3(d) CMA Call Center Transcript

Incident Review

Location of Incident: 453 Worthington St. Springfield, MA

Date of Incident: November 23, 2012

Time of Incident: 17:25

Number of Customers Involved: 1

Did this incident merit review according to 49 CFR 192 Subpart L? NO

Did this incident merit review according to circumstance or performance related issues? YES

Name of Operations Center Manager: Scott Ruble

Name of Facilitator: Brian Normoyle

Was Preliminary Report, 1540C Completed? NO

Description of Incident – What actually happened?

While performing a leak investigation on an odor call at 453 Worthington St Springfield, first responding Utility Technician punctured a 1 1/4" IP plastic inserted service line with a bang bar. 55 PSI Gas released through bar-hole at foundation and into the basement of 453 Worthington. Gas in building eventually ignited, resulting in an explosion.

Scope of Review:

Determine if actions taken by employees prior to and following incident were appropriate and in accordance with CMA policies and procedures. Review lessons learned, current procedures and practices to determine adequacy and prevent reoccurrence.

Name of Employees Attending Review:

o Brian Normoyle	John Rooney	Christopher Warren	Michael Rokosz	Daniel Maslowski
o Brent Alexander	Gregory DeAngelo	Justin Carr		

What could have been done to improve Incident Preparation?

- o Availability of tap card records to CMA Utility Worker General employees to identify service line information.

What actions were taken?

Prior to explosion, response to odor call.: Technician dispatched to 453 Worthington Street Springfield based on call from that location's business manager Matt. The order was dispatched as odor in basement. Upon arrival, the first responding technician zeroed his CGI in free air and proceeded to the entrance of the business. CMA tech smelled a slight odor of gas outside the entrance way of the business. CMA tech was met by the business' manager Matt, who stated that they had been sensing gas outside and in the front entry way when the door was opened, then proceeded to show the CMA tech to the basement. CGI showed no readings in basement, at meter, piping, or around service line penetration through basement wall. CMA tech also observed a soft, clay-like material surrounding the service line on the foundation. Seeing zero reads, and the fact that the odor of gas was more pronounced outside the building than that smelled in the basement, he made the decision to investigate outside the business.

CMA Technician checked a manhole located outside the front of business and his CGI registered zero. He retrieved his bang bar probe from his vehicle and returned to the entrance way of the building to pinpoint the origin of the odor. The technician observed a yellow marking on the sidewalk which he interpreted as a dig safe locate for the gas service. He displaced himself laterally, approximately 2 feet away from that yellow marking and put down his first bar-hole using his bang-bar tool, at the curb and street line. A reading of zero gas was obtained at that bar hole. He then went to the seam between the sidewalk and building foundation and made a second bar-hole, again staying approximately 2 feet to the side of that yellow marking. When the bang bar was extracted from the second hole, blowing gas was escaping. The technician had punctured the medium pressure service line and now had a blowing gas situation. The technician notified the logistics center of his situation and requested a distribution crew, and that he had blowing gas at the building and could not stop it. CMA technician proceeded inside the building ordering an evacuation, and went to the basement where he shut off the meter cock. He observed blowing gas around the service entrance in the basement. Tech made additional calls to logistics requesting Fire Department, and electric service shut off. Evacuations were completed and CGI reads of manholes were being performed while waiting for Distribution crew and additional help checking adjacent properties and substructures.

What was done well?

- Incident response times by all responders
- Hazard recognition, and decision making to evacuate and protect life.
- Thorough survey of area to check for gas migration or damage to underground facilities as a result of the explosion.
- Communications. Excellent teamwork among CMA Leadership and Communications Department to keep the public, emergency responders, and incident investigators well informed and assured that the immediate hazard was eliminated and ensuring CMA's full cooperation.

What improvements could be implemented?

- Review / Revise procedures around utilization of bang bar tools for leak pinpointing.
- Review current tools used for leakage pinpointing.
- Training on bang-bar probe tool safety: depth of insertion, checking point (sharpness), locating facilities prior to bar-holing.
- Training on bang bar tool use: When to use a bang bar when performing a leak investigation.
- Review/Revise procedures allowing tech immediate on-site access to tap cards.

What ideas were generated?

- Distribution vehicle proved to withstand enormous force without toppling or moving and injuring those behind it. Columbia should continue to utilize that style / manufacturer of vehicle.

Lessons learned

- Locate underground facilities prior to bang barring for pinpointing.
- Inability to allow reliance on prior markings as accurately identifying underground structures

3(b) Timeline and sequence of events

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
FIRST SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: December 10, 2012

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-1-2: Provide a sequence of events from the initial odor call to when the Incident occurred. Include all records that demonstrate: (1) receipt time of the initial odor complaint; (2) the arrival time of first responder; (3) a detailed description of the actions the first responder initiated when he arrived at the scene before the line was damaged - and the length of time it took to perform these actions; (4) the time the first responder damaged the gas service; (5) the time the first responder notified Columbia Gas of the damaged facility (include recordings of this notification); (6) the time 453 Worthington Street was evacuated and the count of persons evacuated; (7) the time Dispatch notified the crew and supervisor(s) to report to the location of the damaged facility; (9) the time the Operator notified the Springfield Fire Department and Western Massachusetts Electric Company.

Response: Please see Attachment IR-PL-1-2 (a) for CMA's complete timeline related to this incident.

Regarding the specific times requested:

- (1) CMA received the odor call at 15:25.
- (2) Christopher Warren arrived on-site at 15:49.
- (3) Please see Attachment IR-PL-1-2 (b) for the description of the actions taken by Christopher Warren prior to the line damage.
- (4) - (6) Christopher Warren contacted Logistics at 16:11 to request a street crew for the gas leak. Attachment IR-PL-1-2 (c) is a transcript of the call. The recording is contained on the enclosed disk.
- (7) Logistics contacted the Springfield Distribution Crew at 16:14.
- (9) [sic] Logistics notified the Springfield Fire Department at 16:19 and the Western Massachusetts Electric Company at 16:23.

To: John Rooney

Fr: Jim Murphy

Re: 453 Worthington Street, Springfield, MA Incident November 23, 2012

December 6, 2012

As requested, here is the November 23, 2012 timeline for the above referenced incident. The times, unless otherwise noted, are time stamped in the Columbia Gas of Massachusetts Logistics office in Brockton, MA.

3:25pm: Received call reporting a "possible gas leak" at 453 Worthington Street, Springfield, MA. Caller's name "Matt."

3:29pm: Order dispatched to Service Technician Christopher Warren.

3:29pm: Christopher Warren goes on route to 453 Worthington Street, Springfield, MA.

3:49pm: Christopher Warren arrives on site at 453 Worthington Street, Springfield, MA.

4:11pm: Christopher Warren calls into Logistics Office requesting a street crew to respond as soon as possible to 453 Worthington Street, advising the service was leaking, he could not shut it off, and he had a blowing gas situation.

4:14pm: Logistics contacts Springfield Distribution Crew (Brent Alexander and Greg DeAngelo) and dispatches them to 453 Worthington Street Springfield, MA.

4:16pm: Logistics notifies Field Operations Leader Justin Carr.

4:18pm: Christopher Warren informs Logistics that he needs the Fire Department to respond as soon as possible.

4:19pm: Logistics notifies the Springfield Fire Department requesting Fire Department response to 453 Worthington Street as soon as possible for a gas leak.

4:23pm: Christopher Warren notifies Logistics to call the electric company.

4:23pm: Logistics notifies Connecticut Light & Power and requests that the electric power be turned off to 453 Worthington Street, Springfield, MA because of a gas leak. Logistics provided the cross street location and a contact telephone number.

4:26pm: Christopher Warren requests from Logistics the name of the FOL, informs Logistics that the Fire Department is on site, and the building is being evacuated. There is high pressure gas blowing in the basement.

4:42pm: Christopher Warren calls Logistics and requests additional technicians be dispatched to check the other buildings in the area. Informs Logistics less than twenty (20) people were evacuated.

4:44pm: Utility Worker Dan Maslowski informs Logistics he is en-route to 453 Worthington Street.

4:55pm: (According to Field Force Manager from the GPS on the Company issued cell telephone) Brent Alexander arrives on site at 453 Worthington Street, Springfield, MA.

5:20pm: (Approximate) Greg DeAngelo shuts off the curb valve to 453 Worthington Street.

5:27pm: Dan Maslowski calls Logistics and advises there has been an explosion. All CMA onsite personnel are accounted for.

5:34pm: Logistics utilized ARCOS and made an "All Hands on Deck" call. 139 calls made simultaneously.

5:42pm: Construction Leader Justin Carr calls Logistics and advises all responding support personnel report to the Springfield Operating Center not the incident location.

5:44pm: (Actual 9 minutes 37 seconds) eighteen (18) technicians accepted calls via ARCOS and eight additional technicians called to accept over the land line in Logistics. Total twenty-six (26).

5:56pm: Logistics called the Massachusetts Department of Public Utilities (DPU). Left message on voice mail regarding the incident.

6:00pm: Five (5) additional technicians call Logistics on the land line. Thirty-one (31) CMA Emergency Responders in total available.

6:05pm: (Approximately) Jorge Santi from the DPU called Logistics. Apparently saw the incident on the news.

6:20pm: (Approximately) Jim Murphy called Jorge Santi and reviewed the details as they were known. Jorge indicated he was headed to the incident location and will be joined by Angela Motley and possibly one other member from the DPU.

6:24pm: (Approximately) Brian Normoyle informed Jim Murphy he made a telephonic notification to the Department of Transportation.

7:00pm: (Approximately) Berkshire Gas called Logistics offering Mutual Aid if necessary. Contact them at (413)445-0230, 0231 if Mutual Aid is required.

8:00pm: (Approximately) Insurance carrier ESIS notified. Claim Number: 117354092

I did not document a timeline after 8:00pm. Please let me know if you have any questions.

Upon arrival at the scene, CMA employee Christopher Warren parked his vehicle and noted on his laptop his 15:49 arrival at 453 Worthington Street, Springfield, MA. Mr. Warren telephoned his contact, "Matt" and waited for Matt's arrival. Mr. Warren got out of his vehicle and prepared for his leak investigation. Mr. Warren turned on his Combustible Gas Indicator ("CGI") in the outside free air and zeroed the instrument. When Matt arrived, Matt told Mr. Warren that 453 Worthington Street had been experiencing an odor of gas outside the building near the front door, and they experienced the odor in the front hallway when the front door was opened. Mr. Warren detected a slight odor of natural gas outside the front of the building with his nose. Mr. Warren's CGI registered zero. Mr. Warren entered the building with Matt, went through the ladies room, and downstairs into the basement. The basement was dimly lit. Mr. Warren located the gas service line and observed the line surrounded by a soft, clay-like substance. With his CGI probe, Mr. Warren checked around the service line. His CGI registered zero. Mr. Warren tested the connections from the service entrance to the meter. His CGI registered zero. Based upon the odor of natural gas outside the building, information that the property had been experiencing a natural gas odor outside the building, the packing of the service line with a soft, clay-like material, and no readings of natural gas in the basement, Mr. Warren went up the stairs and began his outside leak investigation. Mr. Warren located a Western Massachusetts Electric Company manhole in front of the building and inserted his CGI probe into the vented top. His CGI registered zero. Mr. Warren observed a yellow marking on the sidewalk consistent with, and in line with, the inside meter he just previously observed. Mr. Warren went to his vehicle and got his barhole probe. With the yellow marking as his point of reference, Mr. Warren stepped off to the right of the line approximately two (2) feet and barholed between the curb and the street. A parked car in the area caused difficulty in barholing. Mr. Warren inserted the extended CGI probe into the barhole. His CGI registered zero. Mr. Warren walked to the foundation of the building and, using the yellow mark as his point of reference, stepped approximately two (2) feet to the right of the line and inserted his barhole between two (2) concrete slabs in the sidewalk next to the foundation of the building. Upon removal of his barhole probe, natural gas began to escape from the hole in the ground. Mr. Warren's best estimate is that twenty (20) minutes elapsed from the time of his arrival 453 Worthington Street to the time natural gas came out of the hole in the ground;

Transcript of call made by Chris Warren to Logistics at 16:11.

Ellie: Columbia Gas this is Ellie

Chris: Ellie its Chris Warren how ya doing?

Ellie: Hey Chris how are you?

Chris: Good, I need a Street Crew here as soon as possible.

Ellie: Okay, whatcha got?

Chris: I got blowing gas out of the ground inside this club, where they were smelling gas.

Ellie: Out of the ground

Chris: The service is leaking, right at the edge of the building

Ellie: Out of the ground?

Chris: I can't shut it off

Ellie: K I will send someone out there as soon as possible.

Chris: Thank you

Ellie: yup, thank you.

Chris: Bye

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
FIRST SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: December 10, 2012

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-1-3: Provide a sequence of events and a description of the Incident. Include all records that demonstrate: (1) the time Columbia Gas crew and supervisor(s) arrived at the Incident; (2) the time Columbia Gas initiated an Emergency Notification to staff; (3) the time Western Massachusetts Electric Company arrived on the scene; (4) the time Western Massachusetts Electric Company turned off the electricity to 453 Worthington Street, Springfield; and (5) the time the Fire Department arrived on the scene.

Response: Please see Attachment IR-PL-1-2 for CMA's complete timeline related to this incident. CMA has requested, but has not as of the time of this filing, received the complete timeline from Western Massachusetts Electric Company regarding their timing. CMA will supplement this response when Western Massachusetts Electric Company's timeline is received.

Please see Attachment IR-PL-1-33 for the Springfield Fire Department's Report.

Regarding the specific times requested:

- (1) Brent Alexander, Lead Operator, arrived on-site at 16:55.
- (2) CMA initiated ARCOS notification at 17:34.
- (3) CMA has been informed that Western Mass Electric arrived on-site at 17:14.
- (4) CMA will provide this information as soon as it is available from Western Mass Electric.
- (5) Based on the Springfield Fire Department Report (see Attachment IR-PL-1-33), the Fire Department arrived at 16:24.

My name is Chris Warren. I am 52 years old. Prior to being hired by Columbia Gas on July 21, 2008 as a Meter Tech, I worked as a locator for On Target.

At approximately 3:30 p.m., I was dispatched to the location on a call for an odor of gas. I parked in the parking lot and telephoned the property's contact person, "Matt," who was to meet me at the site. I waited a few minutes for Matt to arrive, and when he did, Matt said that they had been smelling gas for a while. As I stood in front of the building, I could detect an odor of gas. Matt and I entered the building, walked through the ladies room, and headed down into the basement.

As I entered the basement, my CGI continued to read "zero." I located the service line entering through the foundation and observed that the line was surrounded by a "clay-like material" that felt like soft clay. I detected a slight odor of gas in the basement. I used my CGI probe and checked the area where the service line entered the basement, the associated gas piping, the connections to the gas meter, and the gas meter. My CGI continued to register no readings in the area. I exited the building and located Western Mass. Electric Co. manholes in the street. I inserted my CGI probe into the manhole cover and once again, obtained no reading.

I observed a yellow gas mark on the sidewalk that appeared to be in line with the service I observed in the basement. I went to my truck and got a bang bar and, with the yellow line as my point of reference, stepped off to the side and bar-holed between the curb and the street. I had a difficult time with this first bar hole because of a parked car in the street. I inserted my CGI probe into the bar hole and got no reading.

Again, using the yellow line as his point of reference, I went closer to the building, stepped off to the side of the yellow line, and bar-holed between two sections of concrete

sidewalk near the edge of the building. I could not go down far at all and gas immediately came out. I called dispatch to tell them what happened

I entered the building and told the manager to immediately evacuate the building. I went back into the basement and turned the valve on the service line to the "off" position. I continued to clear people away from the evacuated building, interacted with the responding fire fighters, took CGI readings in numerous manholes, and made additional telephone calls to dispatch.

When the street crew arrived, I informed Brent Alexander what had occurred. I helped them locate the curb box. I assisted the street crew in blowing out debris in the curb box. The curb valve was shut off. The crew and I opened a number of manholes in the area.

I was directed by Brent Alexander to stand behind the truck. Everyone was behind the truck including someone from the City Water Department who was sitting on the ground in the area when the explosion occurred.

Chris Warren

Chris Warren

Date: 12-06-2012

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
FIRST SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: December 10, 2012

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-1-5: Provide the time Columbia Gas received the odor complaint call from the residents of 453 Worthington Street, Springfield, and transcripts of all conversations between the Columbia Gas representative and the caller(s).

Response: CMA received a call from Matt, the manager of Scores, at 15:23. Attachment IR-PL-1-5 is a transcript of the call. The recording is contained on the enclosed disk.

Dispatch: Columbia gas emergency gas leak line this line is recorded

Matt: Yes hi I'm calling uh a possible gas leak at my business

Dispatch: What is the address?

Matt: 453 and a half Worthington street Springfield, Massachusetts

Dispatch: What's the name on the account?

Matt: Uhhhh the corporate name of the company is Sulisants or could be the DBA theatre uhh club 418 Lace or Scores. I don't know if they ever changed the DBA on it but the corporate name is Sulisants.

Dispatch: Okay, I'm only showing one site coming up at 453 Worthington and it's under BSC reality.

Matt: Oh yup that's our , that's the real-estate agent that real-estate it goes through, that's one of our company's. Ya I think I uh at the meters smells like there's a gas leak.

Dispatch: And what is your name?

Matt: My name is Matt, I'm one of the managers, property manager

Dispatch: And a call back phone number?

Matt: 413-626-5094

Dispatch: The odors at the gas meters?

Matt: Wha, uhhh, ya uhhh the gas meters in the basement, seems right above them are near the gas meters and they got a slight sense of gas

Dispatch: And what door are we going to come to for access front, back or side?

Matt: Uh front door on Worthington, if they want they can call me, I'm across the street, and they can call me, I'll be right over there, whenever they are in the neighborhood.

Dispatch: Okay, but so you're saying the address is 453 and a half Worthington?

Matt: Well, sometimes well that's what the postal address is, but sometimes it's posted as 453.

Dispatch: Okay

Matt: That could be the case. There nothing else around this place, nothing on both sides of it

Dispatch: Alright, I'll have someone there within the hour so please watch for them. Okay, they can't

Matt: I appreciate it. I understand.

Dispatch: Alright byebye

Matt: I understand thanks

(Hang up)

EXHIBIT 4

CMA Records of Gas Service Supplying 453 Worthington Street, Springfield

175
 MCULT



Distribution Work Order

Identification:

At House # 453	To House # 	Street Name WORTHINGTON ST	Location Phone 	Work Order # 173460
	Lot # 	Town SPRINGFIELD	Work Phone 	Initiated Date 12/03/93
At Pole # 	To Pole # 	At Intersection 	Customer Account # 	Initiated Time 0722
Kit and Grid # 	To Intersection 	CCS Number 147064-00-000	Source CCS SYSTEM	
Customer Name MIKES OF SPRINGFIELD	Entered By SCULLY	Source Name 		

Work:

Work Code SNEOCB	Work Description SER-NEW-EXT CNST ON-COM-C	Estimated Units 1	Scheduled Date
		Leak Priority 	Employee Assigned
		Cause of Leak 	BSG Crew Assigned
Outgoing Comments INSTALL NEW SERVICE INSERT SPACE "0" "0" "0" 3" E "0" "0" "0" SP "A.M." 733-4051 NO SERVICE RECORD		Job Priority MEDIUM	Contr. Crew Assigned

Pipe Data:

	New Pipe	Exposed Pipe	Retired Pipe
Pipe Size	1.25	1 1/4	16"
Pipe Type	PLASTIC	P.P.	C.S.
Coat Type			B.
Pressure	INTER-MED	T.P.	
Length	25	30'0"	
Cut		4x4	
Depth		4'0"	4"
Year	1993		
Pipe Cond			
Coat Cond			
Pipe Depth			
# of Fits			
Fit Size			
Rate Class			

Other Data:

Anode Inst.	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No
Flow Limiter Installed	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No
Flow Limiter Tagged	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No
Curb Cock Installed	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No
Meter Barrier Installed	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No
Meter Fit Installed	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No
Inside	<input checked="" type="checkbox"/>	
Outside	<input type="checkbox"/>	
Soap Test	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No
Pressure Test	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No
Pounds Square Inch	90	
Elapsed PSI Time	15	

Patch Needed ☒ Yes ☐ No Patch Done ☒ Yes ☐ No Is Work Billable ☐ Yes ☐ No

Enter Other Completion Information And Patch Information on Back

Sketch:

Materials Used
1 1/4 x 1 1/4 x 1 1/4 H.P. welded 3T. tee
1 1/4 steel C.C.
445 = C. box
1 1/4 x 1 1/4 transition sleeve
3" anode
2 x 1 1/2 x 1 1/2 por. lock collar tee
1" lock cork
300' of 1 1/4 P. pipe
50' warning tape

Line of Main _____

Restoration Data:

	Required	Done	Date Done
Sand	<input type="checkbox"/>	<input type="checkbox"/>	
Gravel	<input type="checkbox"/>	<input type="checkbox"/>	
Base Coat	<input type="checkbox"/>	<input type="checkbox"/>	
Cold Patch	<input type="checkbox"/>	<input type="checkbox"/>	
Hot Patch	<input type="checkbox"/>	<input type="checkbox"/>	
Emulsion	<input type="checkbox"/>	<input type="checkbox"/>	
Infra-Red	<input type="checkbox"/>	<input type="checkbox"/>	
Concrete	<input type="checkbox"/>	<input type="checkbox"/>	
Loam & Seed	<input type="checkbox"/>	<input type="checkbox"/>	
Size	<input type="text"/>		
Signature	<input type="text"/>		

Permit Data:

Dig Safe:	Ticket #	Date Effective
Notification:		
Permit Required:		
Town	Date Sent	Date Rec'd
State		
Water Notification:	<input checked="" type="checkbox"/>	Date Called 12-10
Sewer Notification:	<input type="checkbox"/>	Date Called

Stamps:

Completion Data:

Comments:	Re-ran 2" sec. with 1 1/4 P. pipe
Completed Date	12/18/93
Completed Units	1
Signature	Jose Nicole



Distribution Work Order

Project LD.

Identification:

At House	To House	Street Name	Location Phone	Work Order #
453	0	WORTHINGTON ST		6497409-1
Bldg. #	Unit #	Apt. #	Suite #	Town
				SPRINGFIELD
Work Phone	Initiated Date	At Lot	To Lot	At Pole
	03/06/2007			
To Pole	At Intersection	Customer Account #	Initiated Time	
			11:57	
Kit and Grid #	To Intersection	CCS Number	Source	
		0-0-0	EMPLOYEE	
Customer Name	Entered By	Digging Conditions	Source Name	
			ZIEMBA DAVID M	

Work:

Work Code	Work Description	Estimated Units	Scheduled Date
LBSX	SERVICE - LEAK REPAIR	1	03/06/2007
JCIX		Leak Priority	Employee Assigned
		CLASS 1	TROLIO, NICOLA
Outgoing Comments	Cause of Leak	BSG Crew Assigned	
CHECK FOR 910	Joints	TRUCK 386	
	Dig Safe #	Contr. Crew Assigned	
	Job Priority		

Pipe Data:

Other Data:

	New Pipe	Exposed Pipe	Retired Pipe
Pipe Size		8"	
Pipe Type		CI	
Coat Type		LP	
Pressure			
Length			
Cut	S M L		S M L
Depth		40"	
Year		1930	
Pipe Cond.	LN - F - P - VP	LN - F - P - VP	LN - F - P - VP
Coat Cond.	G - MD - ED	G - MD - ED	G - MD - ED
Pit Depth			
# of Fits			
Fit Size			
Rate Class			

Anode Inst.	<input type="checkbox"/>
Flow Limiter Installed	<input type="checkbox"/>
Flow Limiter Tagged	<input type="checkbox"/>
Curb Cock Installed	<input type="checkbox"/>
Meter Barrier Installed	<input type="checkbox"/>
Meter Fit Installed	<input type="checkbox"/>
Inside	<input type="checkbox"/>
Outside	<input type="checkbox"/>
Soap Test	<input checked="" type="checkbox"/>
Pressure Test	<input type="checkbox"/>
Pounds/Square Inch	
Elpsd. PSI Time	
Patch Size Length	
Width	

Restoration Needed	<input type="checkbox"/>	Restoration Done	<input type="checkbox"/>	Bill to Customer?	<input type="checkbox"/>
--------------------	--------------------------	------------------	--------------------------	-------------------	--------------------------

Columbia Gas of Massachusetts
re: 453 Worthington St, Springfield, MA (11-23-12)
Attachment IR-PL-2-25
Materials Used Page 2 of 4

Restoration Data:

Dig Safe:	Ticket #	Date Effective
Notification:	_____	_____
	_____	_____
Permit Required:		
	Date Sent	Date Rec'd
Town	_____	_____
State	_____	_____
	Permit #	_____

Water Notification:		
	Date Called	_____
Sewer Notification:		
	Date Called	_____

Completion Data:

Comments:	2nd K17 18' to 24' in 24' in of E 5' 45"
Completed Date	Date Started
3-12-07	3-12-07
Completed Units	Signature
1	W. Trebo

Columbia Gas of Massachusetts
re: 453 Worthington St, Springfield, MA (11-23-12)
Attachment IR-PL-2-25
Page 3 of 4

386

DEFO RGE

Total Hours Worked	9
--------------------	---

SUPERVISOR APPROVAL

Distribution department Daily Crew Sheet

Columbia Gas of Massachusetts
re: 453 Worthington St, Springfield, MA (11-23-12)
Attachment IR-PL-2-25
Page 4 of 4

Date Vehicle #

3-6-07 386

Empl # Name

386	TILLOTT
1086	DEFORGE


Job	Work Order Number	Street #	Street Name	Town Code	Job Time	Pay Rate
	6467118-1	49	LYMAN ST	SH	2	1
	6497166	49	TOLCATT ST	SP	1	i
	6467118-1	49	LYMAN ST	SH	1	1
	6407409	453	WORTHINGTON ST	SP	1/2	1 1/2
	"	453	WORTHINGTON ST	SP	2	1
	6448595	50	COLLEGE ST	SH	2	1

Total Hours Worked 8 1/2

Daily Work Comments

Job	Arrive	Depart	Work Description	Complete ?
	:	:		
	:	:		
	:	:		
	:	:		
	:	:		
	:	:		
	:	:		
	:	:		
Lunch	:	:		

SUPERVISOR APPROVAL



COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
SECOND SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: January 4, 2013

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-2-25: Refer to CMA response to IR PL 1-24. Ticket 175395102 (3/6/2007), comments note: "found .30% gas at wall called for street stan" and "service has been re-run 000.00% LEL." Provide a detailed explanation regarding CMA's activities on this date, including actions taken to address the conditions found and actions taken to eliminate the hazard.

Response: The work order (WO-175395102) (3/6/2007) submitted in response to IR-PL-1-24, was for a meter change-out on a periodic test interval. The meter technician discovered and reported a gas reading at the basement wall where he was working. The comment "service has been re-run" is not accurate. Attachment IR-PL-2-25 contains the WOMS Distribution order (WO-6497409) which was issued that same day for a distribution crew repair. On March 6, 2007, the distribution crew responded to 453 Worthington and made a temporary repair to make it safe. That same crew returned on March 12, 2007, to seal the leaking joint as noted on the WO-6497409. Attachment IR-PL-2-25, pages 3 and 4 of 4 contain copies of the distribution crew worksheets.

WORK ORDER

NO. **2**

DATE **8/27/80**

TIME REC'D _____ AM PM

SPRINGFIELD

PUNCHED

WORK AT **In Front** **453 Worthington St.**

TOWN CODE **09**

ACCOUNT OR AUTH. NO. **254-82**

NAME _____ ACCT. NO. _____

BILL TO _____ BILL AMT. _____

PREP. BY **DK** REPORTED BY **3** **A. Smith** VIA **4**

WORK OR CONDITIONS _____

IS PERMIT REQ? _____ PICK-UP? _____
TOWN _____ DATE SENT _____
STATE _____ DATE REC'D _____

NOTIFICATIONS

☐ ELECTRIC CO. ☐ WATER DEPT.
☐ TELEPHONE CO. ☐ SEWER DEPT.

Cut off service - 2" L.P. Service

GIVEN TO _____

WORK TO BE DONE BY: ☒ COMPANY ☐ CONTRACTOR

Est. Cost. _____

WORK CODE

DISTRICT

PRIORITY

EST. MAN HRS.

NO. OF MEN

SIZE

PRESSURE

SIZE OR FIT

EST. FT. OR UNITS

SCHEDULED DATE

GIVEN TO _____

DISP. TO _____

BY _____

VIA _____

TIME _____ DATE _____

WORK DONE:

EXISTING PIPE DATA

WORK CODE	SIZE	PIPE TYPE	PRES.	SOIL	FEET OR UNITS	CAUSE OF LEAK	SIZE	COND.	TYPE	COATING	PR. OF INST.
5209	2	85	1	SA	30	9	3	8	85	2	30
5209	2	85	1	SA	30	9	3	8	85	4	30
						9		8			
						9		8			

MEASUREMENTS

	FEET	IN.	DEPTH OF	FEET	IN.
SERVICE LGTH.			MAIN	3	00
TEE TO CURB S.O.			SERVICE	3	00
SHUT OFF TO END			PITS		
COCK TO ANODE					

PATCH REQUIRED? **NO** SIZE **2"**

SKETCH:

Service cut off main in Road with Patch

EQUIPMENT

HOURS

CONTRACTOR

BACKHOE

WELDER

COMPRESSOR

POLICE OFFICER

TRUCK NO. **51-14**

SERVICE CREW

MAIN CREW

PATCH CREW

METER FIT REM'D

YES NO

REG. REM'D

YES NO

METER FIT INS'L

YES NO

COMMENTS:

cut off main

material used 2" = 2" line

cut

no further repair

LINE OF SERVICE

LINE OF MAIN

FOR OFFICE USE ONLY

BY **NGR**

DATE **8-27-80**

REPORT _____ MF _____ RENEWAL _____ STUB _____ BILLING _____ POOR _____ NP _____

PIPE _____ DUP _____ ABAND. _____ BKWD _____ OTHER _____

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
FIRST SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: December 10, 2012

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-1-38: Provide a copy of the pressure chart of the nearest regulator station servicing
Worthington Street, on November 23, 2012.

Response: Please see Attachment IR-PL-1-38.

SCADA Report

RTU State: MASSACH

RTU Name: BLIS

RTU Owner: BSG

RTU Description: BLS-Blis St. Station

From Calendar Date: 2012-11-15

To Calendar Date: 2012-11-25

Calendar Date	Calendar Hour	Current Reading	Average Reading	Maximum Reading	Minimum Reading
2012-11-22	0	53.33	53.33	53.33	53.33
2012-11-22	1	53.33	53.33	53.33	53.33
2012-11-22	2	53.33	53.33	53.33	53.33
2012-11-22	3	53.33	53.33	53.33	53.33
2012-11-22	4	53.33	53.33	53.33	53.33
2012-11-22	5	53.33	53.33	53.33	53.33
2012-11-22	6	53.33	53.33	53.33	53.33
2012-11-22	7	53.33	53.33	53.33	53.33
2012-11-22	8	53.33	53.33	53.33	53.33
2012-11-22	9	53.33	53.33	53.33	53.33
2012-11-22	10	53.33	53.33	53.33	53.33
2012-11-22	11	53.33	53.33	53.33	53.33
2012-11-22	12	53.33	53.33	53.33	53.33
2012-11-22	13	53.33	53.33	53.33	53.33
2012-11-22	14	53.33	53.33	53.33	53.33
2012-11-22	15	53.33	53.33	53.33	53.33
2012-11-22	16	53.33	53.33	53.33	53.33
2012-11-22	17	53.33	53.33	53.33	53.33
2012-11-22	18	53.33	53.33	53.33	53.33
2012-11-22	19	53.33	53.33	53.33	53.33
2012-11-22	20	53.33	53.33	53.33	53.33
2012-11-22	21	53.33	53.33	53.33	53.33
2012-11-22	22	53.33	53.33	53.33	53.33
2012-11-22	23	53.33	53.33	53.33	53.33
2012-11-23	0	53.33	53.33	53.33	53.33
2012-11-23	1	53.33	53.33	53.33	53.33
2012-11-23	2	53.33	53.33	53.33	53.33
2012-11-23	3	53.33	53.33	53.33	53.33
2012-11-23	4	53.33	53.33	53.33	53.33
2012-11-23	5	53.33	53.33	53.33	53.33
2012-11-23	6	53.33	53.33	53.33	53.33
2012-11-23	7	53.33	53.33	53.33	53.33
2012-11-23	8	53.33	53.33	53.33	53.33
2012-11-23	9	53.33	53.33	53.33	53.33
2012-11-23	10	53.33	53.33	53.33	53.33
2012-11-23	11	53.33	53.33	53.33	53.33
2012-11-23	12	53.33	53.33	53.33	53.33
2012-11-23	13	53.33	53.33	53.33	53.33
2012-11-23	14	53.33	53.33	53.33	53.33
2012-11-23	15	53.33	53.33	53.33	53.33
2012-11-23	16	53.33	53.33	53.33	53.33
2012-11-23	17	53.33	53.33	53.33	53.33
2012-11-23	18	53.33	53.33	53.33	53.33
2012-11-23	19	53.33	53.33	53.33	53.33
2012-11-23	20	53.33	53.33	53.33	53.33
2012-11-23	21	53.33	53.33	53.33	53.33
2012-11-23	22	53.33	53.33	53.33	53.33
2012-11-23	23	53.33	53.33	53.33	53.33
2012-11-24	0	53.33	53.33	53.33	53.33
2012-11-24	1	53.33	53.33	53.33	53.33
2012-11-24	2	53.33	53.33	53.33	53.33
2012-11-24	3	53.33	53.33	53.33	53.33
2012-11-24	4	53.33	53.33	53.33	53.33
2012-11-24	5	53.33	53.33	53.33	53.33

EXHIBIT 5

Photographs of Incident Area:

- 5(a) Aerial View of Incident Site
- 5(b) Ground View of Incident Site
- 5(c) The Damaged Gas Service Supplying 453 Worthington Street
In Situ
- 5(d) The Damaged Gas Service with Probe Bar
- 5(e) The Gas Service Connected to the Gas Main in
Worthington Street
- 5(f) The Faded Yellow Line in Relation to the Damaged
Gas Service In Situ
- 5(g) Gas Service Regulator and Gas Meter
- 5(h) Gas Service Piping Inside 453 Worthington Street

Exhibit 5(a) - Aerial View of Incident Site



Exhibit 5(b) - Ground View of Incident Site



Exhibit 5(c) - The Damaged Gas Service Supplying 453 Washington Street In Situ



Exhibit 5(d) - The Damaged Gas Service With Probe Bar



Exhibit 5(e) - Gas Service Connected to the Gas Main in Worthington Street




Exhibit 5(f) - The Faded Yellow Line In Relation to the Damaged Service Line In Situ




Exhibit 5(g) - Gas Service Regulator



Exhibit 5(g) - Gas Meter



Exhibit 5(h) - Gas Service Piping Inside 453 Worthington Street




EXHIBIT 6

Records of Cast Iron and Steel Main Underlying Worthington Street

WORK ORDER

SPRINGFIELD

NO. **2** 020325

DATE **May 1, 1980**

TIME REC'D **AM** PM

WORK AT: **Worthington St.**

NUMBER

STREET

TOWN CODE

NAME

ACCT. NO.

BILL TO

BILL AMT.

PREP BY

NB

REPORTED BY

3

CHE

VIA

4

WORK OR CONDITIONS

Run a 16" main I.P. W.S. starting at 16" 90° weld bend 8' 0" W of E line of Alert St. 23' 0" S of N line of Worthington St. running 2125' 18" 10' (tie-in) 28' 0" E of E line of E. Columbus Ave. 18' 0" S of N line of Worthington St.

ACCOUNT OR AUTH. NO.

3627-601

IS PERMIT REQ? **Yes**

PICK-UP?

TOWN

DATE SENT

STATE

DATE REC'D

May 14 1980

NOTIFICATIONS

ELECTRIC CO

WATER DEPT.

TELEPHONE CO

SEWER DEPT.

GIVEN TO **H.K.**

WORK TO BE DONE BY:

☐ COMPANY

☒ CONTRACTOR

Hallen

Est. Cost

WORK CODE

M 2

DISTRICT

SIZE

16

PRIORITY

PRESSURE

2

EST. MAN HRS

SIZE OR FIT

EST. FT. OR UNITS

21 25

NO. OF MEN

SCHEDULED DATE

GIVEN TO

DISP. TO

BY

VIA

TIME

DATE

WORK DONE:

WORK CODE	SIZE	PIPE TYPE	PRES.	SOIL	FEET OR UNITS	CAUSE OF LEAK	EXISTING PIPE DATA	PIPE	COND.	TYPE	TYPE	COND.	INST.
M 216	16	CS	2	FM	2124			16	CS	CS	B	1	64

MEASUREMENTS

SERVICE LGTH.	FEET	IN.	DEPTH OF MAIN	FEET	IN.
TEE TO CURB S.O.				3	06
SHUT OFF TO END					
COCK TO ANODE					

EQUIPMENT	HOURS	CONTRACTOR
BACKHOE		
WELDER		
COMPRESSOR		
POLICE OFFICER		
TRUCK NO.		

METER FIT REM'D ☐ YES ☒ NO REG. REM'D ☐ YES ☒ NO METER FIT INS'L ☐ YES ☒ NO

COMMENTS: **Install 16" main I.P. W.S. starting at 16" 90° weld bend 8' 0" W of E line of Alert St. 23' 0" S of N line of Worthington St. running 2125' 18" 10' (tie-in) 28' 0" E of E line of E. Columbus Ave. 18' 0" S of N line of Worthington St.**

PATCH REQUIRED? ☐ SIZE

SKETCH:
RUN a 16" I.P. Main.
Starting at 16" inch 39-40 Drive Severe
26 ft 3 in E of E line of E. Columbus Ave
18 ft 6 in S of N line of Worthington St
Running 2124 ft to 16" 90° Bend
E. 0 in W of E line of Alert St
23 ft 0 in S of N line of Worthington St

LINE OF SERVICE
LINE OF MAIN

FOR OFFICE USE ONLY



Distribution Work Order

Project I.D.



Identification:

At House 453	To House 0	Street Name WORTHINGTON ST	Location Phone	Work Order # 6497409-1
Bldg. #	Unit #	Apt. #	Suite #	Town SPRINGFIELD
At Lot	To Lot	At Pole	To Pole	Work Phone
At Intersection	Customer Account #	Initiated Date 03/06/2007	Initiated Time 11:57	
Kit and Grid #	To Intersection	CCS Number 0-0-0	Source EMPLOYEE	
Customer Name	Entered By	Digging Conditions	Source Name ZIEMBA DAVID M	

Work:

Work Code LRSX JCIX	Work Description SERVICE - LEAK REPAIR	Estimated Units 1	Scheduled Date 03/06/2007
		Leak Priority CLASS 1	Employee Assigned TROMIO, NICOLA
Outgoing Comments CHECK FOR 910	Cause of Leak	PSG Crew Assigned TRUCK 386	
	Dig Safe #	Contr. Crew Assigned	
	Job Priority		

Pipe Data:

	New Pipe	Exposed Pipe	Retired Pipe
Pipe Size			
Pipe Type			
Coat Type			
Pressure			
Length			
Cut	S M L		S M L
Depth			
Year			
Pipe Cond.	LN F P VP	LN F P VP	LN F P VP
Coat Cond.	G MD ED	G MD ED	G MD ED
Pit Depth			
of Fits			
Fit Size			
Rate Class			

Other Data:

Anode Inst.	<input type="checkbox"/>
Flow Limiter Installed	<input type="checkbox"/>
Flow Limiter Tagged	<input type="checkbox"/>
Curb Cock Installed	<input type="checkbox"/>
Meter Barrier Installed	<input type="checkbox"/>
Meter Fit Installed	<input type="checkbox"/>
Inside	<input type="checkbox"/>
Outside	<input type="checkbox"/>
Soap Test	<input checked="" type="checkbox"/>
Pressure Test	<input type="checkbox"/>
Pounds/Square Inch	
Elpsd. PSI Time	
Patch Size	
Length	
Width	

Restoration Needed ☐

Restoration Done ☐

Bill to Customer? ☐

Sketch:

	Materials Used	
	1-8" QUICK KIT	

Line of Main _____

Restoration Data:

	Required	Done	Date Done
Sand	<input type="checkbox"/>	<input type="checkbox"/>	
Gravel	<input type="checkbox"/>	<input type="checkbox"/>	
Base Coat	<input type="checkbox"/>	<input type="checkbox"/>	
Cold Patch	<input type="checkbox"/>	<input type="checkbox"/>	
Hot Patch	<input type="checkbox"/>	<input type="checkbox"/>	
Flow Fill	<input type="checkbox"/>	<input type="checkbox"/>	
Infra-Red	<input type="checkbox"/>	<input type="checkbox"/>	
Concrete	<input type="checkbox"/>	<input type="checkbox"/>	
Loam & Seed	<input type="checkbox"/>	<input type="checkbox"/>	
Other	<input type="checkbox"/>	<input checked="" type="checkbox"/>	DCE
Size			
Signature			

Permit Data:

Dig Safe:	Ticket #	Date Effective
Notification:		
Permit Required:		
	Date Sent	Date Rec'd
Town <input type="checkbox"/>		
State <input type="checkbox"/>		
Water Notification: <input type="checkbox"/>	Date Called _____	
Sewer Notification: <input type="checkbox"/>	Date Called _____	

Stamps:

Completion Data:

Comments:	QUICK KIT 1-8" JOINT LOCATION 29 FT W OF E B. 453	
Completed Date	3-12-12	Date Started
Completed Units	1	Signature
		W. T. ...

Columbia Gas
of Massachusetts
A NISource Company

Distribution Work Order

Project I.D.

Identification:

At House	To House	Street Name	Location Phone	Work Order #
500	0	WORTHINGTON ST		7927279-1
Bldg. #	Unit #	Apt. #	Suite #	Town
				SPRINGFIELD
At Lot	To Lot	At Pole	To Pole	At Intersection
Kit and Grid #	To Intersection	CMS #	Initiated Date	Initiated Time
		0-0-0	01/06/2012	11:22
Customer Name	Entered By	Digging Conditions	Source	Source Name
			LEAK SURVEY	

Work:

Work Code	Work Description	Estimated Units	Scheduled Date
LRSX	SERVICE - LEAK REPAIR		01/06/2012
COMPLETED JC		Leak Priority	Employee Assigned
		CLASS 1	BAKER, JOHN J
Outgoing Comments		Cause of Leak	BSG Crew Assigned
PER JOHN SAPELLI, 85% OVER SERVICE, AND 6% GAS INSIDE AT THE WALL			BAKER, JOHN CRE
(Cross # file) with Alert St		Dig Safe #	Contr. Crew Assigned
		Job Priority	

Pipe Data:

	New Pipe	Exposed Pipe	Retired Pipe	Internal Insp.
Pipe Size		4"	4"	4"
Pipe Type		CI	CI	CI
Coat Type				
Pressure		Low	Low	Low
Length			120'	
Cut	S M L		S M L	
Depth		36"	36"	36"
Year		1930	1930	1930
Pipe Cond.	LN F P VP	LN F (P) VP	LN F (P) VP	LN F (P) VP
Coat Cond.	G MD ED	G MD ED	G MD ED	
Pit Depth				
# of Fits				
Pit Size				

Other Data:

Anode Inst.	Yes	No
Flow Limiter Installed	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Flow Limiter Tagged	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Curb Cock Installed	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Meter Barrier Installed	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Meter Fit Installed	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Inside Location: FBRL		
Outside Location: FBRL		
Soap Test	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Pressure Test	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Pounds/Square Inch		
Elapsed PSI Time		
PLV Installation	Yes	No
	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Sketch:

CUT OFF location	4" CI line Cap
13' S OF N line Worthington St	3 Rls Wax Tape
17' W OF W line #500 Worthington St	4" wooden plug
11' E OF Electric manhole	3 lb Anode
18'6" W OF E line Albert St	
18' E OF light pole # 1695	
822	

T-CC: _____

CC-Riser: _____

Restoration Data:

	Required	Done	Size	Date Done
Base Coat	<input type="checkbox"/>	<input type="checkbox"/>		
Cold Patch	<input type="checkbox"/>	<input type="checkbox"/>		
Hot Patch	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	6x6	1/8/12
Infra-Red	<input type="checkbox"/>	<input type="checkbox"/>		
Concrete	<input type="checkbox"/>	<input type="checkbox"/>		
Loam & Seed	<input type="checkbox"/>	<input type="checkbox"/>		
Other	<input type="checkbox"/>	<input type="checkbox"/>		

Permit Data:

Dig Safe:	Ticket #	Date Effective
Notification:	_____	_____
Permit Required:		
Town	Date Sent	Date Rec'd
State	_____	_____
Water Notification:	<input type="checkbox"/>	Date Called _____
Sewer Notification:	<input type="checkbox"/>	Date Called _____

Completion Data:

Comments:		
CUT + Capped Main on Worthington St Heading N down Albert St W of R.R. 1st Main on Albert St		
Start Date	Completed Date	
1/6/12	1/8/12	
Completed Units	Signature	Employee #
1	[Signature]	0793



Manual Distribution Work Order

Project I.D.

Identification:

At House 500	To House	Street Name Worthington St	Location Phone	Work Order # 7930306
Bldg. #	Unit #	Apt. #	Suite #	Town SPfld
At Lot 33/31	To Lot	At Pole	To Pole	At Intersection Alert St
Kit and Grid #	To Intersection	CMS #	Source	Initiated Date 1/16/12
Customer Name	Entered By	Digging Conditions	Source Name	

Work:

Work Code JCI	Work Description Completed SP	Estimated Units	Scheduled Date
Leak Priority	Cause of Leak	Employee Assigned Baker	BSG Crew Assigned 2377
Dig Safe #	Job Priority	Contr. Crew Assigned	

Outgoing Comments
Clamped 4" Joint on Tee At Main cut off

Pipe Data:

	New Pipe	Exposed Pipe	Retired Pipe	Internal Insp.
Pipe Size		4"		
Pipe Type		CI		
Coat Type		Low		
Pressure				
Length				
Cut	S M L		S M L	
Depth		40"		
Year		1930		
Pipe Cond.	LN - F - P - VP	LN - F - P - VP	LN - F - P - VP	LN - F - P - VP
Coat Cond.	G - MD - ED	G - MD - ED	G - MD - ED	
Pit Depth				
# of Fits				
Fit Size				

Other Data:

Anode Inst.	Yes	No
Flow Limiter Installed	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Flow Limiter Tagged	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Curb Cock Installed	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Meter Barrier Installed	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Meter Fit Installed	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Inside Location: FBRL		
Outside Location: FBRL		
Soap Test	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Pressure Test	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Pounds/Square Inch		
Elpsd. PSI Time		
PLV Installation	Yes	No
	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Sketch:

Clamp location

15' S of N Line Worthington St
18'6" W of E Line Alert St
11' E of Electric Manhole
9' S of Electric Manhole

Materials Used

4" Kwik-Kot

T-CC: _____

CC-Riser: _____

Restoration Data:

	Required	Done	Size	Date Done
Base Coat	<input type="checkbox"/>	<input checked="" type="checkbox"/>	3x5	
Cold Patch	<input type="checkbox"/>	<input checked="" type="checkbox"/>	5x5'	1/10/12
Hot Patch	<input type="checkbox"/>	<input type="checkbox"/>		
Infra-Red	<input type="checkbox"/>	<input type="checkbox"/>		
Concrete	<input type="checkbox"/>	<input type="checkbox"/>		
Loam & Seed	<input type="checkbox"/>	<input type="checkbox"/>		
Other	<input type="checkbox"/>	<input type="checkbox"/>		

Permit Data:

Dig Safe: _____ Ticket # _____ Date Effective _____

Notification: _____

Permit Required:

Date Sent _____ Date Rec'd _____ Permit # _____

Town ☐ _____

State ☐ _____

Water Notification: ☐ Date Called _____

Sewer Notification: ☐ Date Called _____

Completion Data:

Comments:

Clamped 4" joint on fec at
Main cut off

Start Date

1/7/12

Completed Date

1/10/12

Completed Units

1

Signature

Robert Baker

Employee #

0793

EXHIBIT 7

CMA Facilities' Markout Completion Report
454 Worthington Street, August 18, 2011

Folder: Gary Whalen; Assigned To: Gary Whalen

-----SEE46899949492366===MIX===

Content-Transfer-Encoding: quoted-printable

Content-Type: text/plain

(DIG SAFE SYSTEM, INC - MA) 08/18/2011 12:18:50

-AB	-AJ	-GM	-J8
-ML	-NE	-ON	-QC
-RJ	-SV	-US	49-WG CMAGAS
-WM			

***** EMERGENCY *****

TIME..12:18 DATE..08/18/2011

REQUEST NO...20113408026

STATE.....MASSACHUSETTS
MUNICIPALITY..SPRINGFIELDADDRESS..454
STREET...WORTHINGTON STNEAREST CROSS STREET 1..CHESTNUT ST
NEAREST CROSS STREET 2..FAIRBANKS PL-----
NATURE OF WORK..EMERG ELEC CABLE FAULT REPAIREXTENT OF WORK
IN THE ST & SDWALK AREA
CREW IS ONSITE

AREA IS PREMARKED..YES

START DATE.....08/18/2011 START TIME..13:00CALLER.....GENE ROUSSEAU
TITLE.....OWNER
RETURN CALL....ANY TIME
PHONE #.....413-736-7176
FAX #.....413-739-4569
ALT. PHONE #....413-531-9497
EMAIL ADDRESS...
CONTRACTOR.....ROUSSEAU BROS INC
ADDRESS.....32 WISHING WELL WY
CITY.....W. SPRINGFIELD
STATE.....MA
ZIP.....01089
EXCAVATOR DOING WORK..SAME

-----SEE46899949492366===MIX=====

Audit History:**8/18/2011 12:20:04 PM: Received**

DETAILS: Ticket received for registration code WG

8/18/2011 12:20:04 PM: County Assumed

DETAILS: County *HAMPDEN* was assumed because only one place *SPRINGFIELD* was found in the state of *MA*.

8/18/2011 12:20:04 PM: Ticket Queued

DETAILS: Ticket queued for delivery

8/18/2011 12:20:07 PM: Ticket Delivered

DETAILS: Ticket successfully sent to dsperry@nisource.com

8/18/2011 12:22:12 PM: Put in Folder

DETAILS: Put in Gary Whalen by digsafe digsafe

8/18/2011 12:22:12 PM: Assigned

DETAILS: Assigned to Gary Whalen by digsafe digsafe

NOTE: Assigned on folder placement

8/18/2011 1:47:28 PM: Responded

DETAILS: marked in field: added by Gary Whalen, Locate Time: 8/18/2011 1:20:22 PM, Units of Work: 1.00

NOTE: p 2 mains, no active rec's of svc found, per off. mgr, they use oil

EXHIBIT 8

CMA Witness Statements

My name is Brent Alexander. I am 58 years old. I have worked for Columbia Gas for 39 years. My title is "Lead Operator" and my normal work shift is 7:00 a.m – 3:30 p.m. Monday through Friday.

On November 23, 2012 I worked my normal hours and I was also on "stand by." At approximately 4:15 p.m., I was on my way home when I got a call from dispatch and was informed that there was gas blowing into the building at 453 Worthington Street and Chris Warren was at the location. I returned to the Springfield facility, got into my Crew truck, and rode to the scene with Greg DeAngelo. When I arrived on the scene, Chris Warren explained to me that there was blowing gas around the service in the basement of 453 Worthington Street.

I looked for the curb box in the street and located one that I believed serviced the building. My crew and I blew out debris from the curb box with air. When I was able to see the valve, it appeared to be in the "closed" position in relationship to the main. I went to my truck, pulled up the map to the location on my laptop, and discovered that the service line came off the main in a 90 degree angle. I yelled to Greg DeAngelo to turn it off, which Greg did. I also told the crew to pull the manholes in the street as they were getting gas readings of 90%. After the service line was shut down, and the manhole covers had been pulled, the manhole gas readings vented to zero.

The entire crew went to the bar hole area near the foundation and the first CGI reading was 57% which immediately dropped to 51%. Seeing this drop in the gas level prompted me to immediately order everyone to get behind the truck. The explosion then occurred.


 12-5-12

Brent Alexander

My name is Dan Maslowski. I am 47 years old. I have worked at Columbia Gas for 21 years. I am currently a Utility Worker – General. My normal working hours are noon – 8:30 p.m., Monday through Friday.

On November 23, 2012, I saw Brent Alexander driving in the Springfield yard. He informed me that “Chris” had a gas leak. I determined that it was Chris Warren so I called Chris and left a message. Chris called me back and said that he had gas in the building and the Fire Department was on site.

I headed out to Worthington Street. When I arrived, the Fire Department had the area blocked off. I spoke to Chris Warren and then began to test gas readings in manholes. Brent Alexander arrived and I assisted with the air hose used to clear debris out of the valve box. I continued to check gas readings in manholes toward Chestnut Street. I went back to 453 Worthington Street as gas readings near the building were being taken. Brent Alexander told us to get behind the truck. The explosion then occurred.



Dan Maslowski

Dated: 12-5-2012

My name is Greg DeAngelo. I am 58 years old. I have worked at Columbia Gas for 22 years. I am currently employed by Columbia Gas as a Utility Worker.

My normal working hours are 6:00 a.m. – 2:30 p.m. Monday through Friday. On Friday, November 23, 2012, I was on vacation but was on "stand by." I received a call at approximately 4:15 p.m. from the Integration Center and was told that gas was blowing into a building and that Brent Alexander would meet me in the yard.

I immediately left my home and traveled approximately 8 miles to the Springfield yard. I rode in the truck with Brent to Worthington Street. When we arrived, we located and blew out debris from the curb box. The valve appeared to be already in a closed position, and Brent went to a reference map in the truck and he then yelled for me to turn the valve, which I did.

Other Columbia Gas Utility Workers informed us that they were getting approximately 90% gas readings in the manholes, and I told Brent I would begin popping covers, which I did. Thereafter Brent instructed all of us to get behind the truck, which we did, and the explosion occurred.


Greg DeAngelo

Dated: 12-4-12

My name is Mike Rokosz. I am 42 years old. I was hired by Columbia Gas Company in 2006 as a Locator Technician and am currently a Utility Worker. My normal working hours are from noon - 8:30 p.m. Tuesday through Friday, and Saturday from 8:00 a.m. - 4:30 p.m.

On November 23, 2012 at approximately 4:30 p.m., I was on duty when I got a call from the Integration Center requesting assistance on Worthington Street for a gas leak. When I arrived, Brent Alexander, Chris Warren, Justin Carr, Greg DeAngelo and Dan Maslowski were already at the scene. I was requested to check gas reading levels in manholes, which I did. Brent Alexander directed all of us to get behind the company truck and thereafter the explosion occurred.



Mike Rokosz

Dated: 12/04/12

My name is Justin Carr. I am 31 years old. I have been employed by Columbia Gas for approximately five years, and am currently a Construction Supervisor. My normal business hours are 7:00 a.m. – 3:30 p.m. Monday through Friday.

On November 23, 2012, I was the on call supervisor. At approximately 4:20 p.m., I got a call from dispatch informing me Chris Warren had a leak and Crew Chief Brent Alexander and Greg DeAngelo were on their way to the scene. Approximately ten minutes later, I received a call from Chris Warren, advising me he had just evacuated a night club and the Fire Department was on the scene.

I arrived at Worthington Street shortly before 5:00 p.m. Upon arrival, I was briefed on the activities of CMA employees, and was informed about the extent of the evacuation. The Springfield Fire Department was further evacuating the area. I was told the electric company had been called to cut the power. Brent Alexander's crew was blowing out a curb box. It appeared that the valve was in the closed position, so Brent and I reviewed the service maps for the area and determined that the valve was in the "on" position. Greg DeAngelo was instructed to turn the valve off. I observed technicians obtaining gas readings from the manholes and was informed that the gas readings were venting down. When the electric company arrived, they spoke directly with the Fire Department near the intersection of Worthington Street and Chestnut Street. I was with CMA employees and an employee of the City of Springfield Water Department behind the Columbia Gas truck at the time of the explosion.


Justin Carr

Dated: 12/10/12

EXHIBIT 9

Drug and Alcohol Test Results (redacted)

- Investigation identified maintenance activities that affected control room operations, procedures, and/or controller response	
- Investigation identified areas other than those above	
Describe:	
PART F - DRUG & ALCOHOL TESTING INFORMATION	
1. As a result of this Incident, were any Operator employees tested under the post-accident drug and alcohol testing requirements of DOT's Drug & Alcohol Testing regulations?	Yes
- If Yes:	
1a. Specify how many were tested:	6
1b. Specify how many failed:	0
2. As a result of this Incident, were any Operator contractor employees tested under the post-accident drug and alcohol testing requirements of DOT's Drug & Alcohol Testing regulations?	No
- If Yes:	
2a. Specify how many were tested:	
2b. Specify how many failed:	
PART G - CAUSE INFORMATION	
Select only one box from PART G in shaded column on left representing the Apparent Cause of the Incident, and answer the questions on the right. Describe secondary, contributing, or root causes of the Incident in the narrative (PART H).	
Apparent Cause:	G8 - Other Incident Cause
G1 - Corrosion Failure – only one sub-cause can be picked from shaded left hand column	
Corrosion Failure Sub-Cause:	
- If External Corrosion:	
1. Results of visual examination:	
- If Other, Specify:	
2. Type of corrosion:	
- Galvanic	
- Atmospheric	
- Stray Current	
- Microbiological	
- Selective Seam	
- Other	
- If Other, Describe:	
3. The type(s) of corrosion selected in Question 2 is based on the following:	
- Field examination	
- Determined by metallurgical analysis	
- Other	
- If Other, Describe:	
4. Was the failed item buried under the ground?	
- If Yes:	
4a. Was failed item considered to be under cathodic protection at the time of the incident?	
- If Yes, Year protection started:	
4b. Was shielding, tenting, or disbonding of coating evident at the point of the incident?	
4c. Has one or more Cathodic Protection Survey been conducted at the point of the incident?	
If "Yes, CP Annual Survey" – Most recent year conducted:	
If "Yes, Close Interval Survey" – Most recent year conducted:	
If "Yes, Other CP Survey" – Most recent year conducted:	
- If No:	
4d. Was the failed item externally coated or painted?	
5. Was there observable damage to the coating or paint in the vicinity of the corrosion?	
6. Pipeline coating type, if steel pipe is involved:	
- If Other, Describe:	
- If Internal Corrosion:	
7. Results of visual examination:	
- If Other, Describe:	
8. Cause of corrosion (select all that apply):	
- Corrosive Commodity	

EXHIBIT 10

CMA First Responder Record of Prior Damages to Facilities

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
FIRST SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: December 10, 2012

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-1-11: In the last three years, has the first responder, damaged any other company operated facilities (services or mains) as a result of leakage survey investigations? Provide all records for damages that CMA identifies.

Response: CMA has no record of Christopher Warren damaging Company facilities during his employment with CMA.

EXHIBIT 11

Post Incident Odorant Test Results

Columbia Gas of Massachusetts
Springfield Division
Odorant Test Point

DOT 192.625
Revised 8/5/08

Employee Signature  Employee # 121709

Town SPRINGFIELD

Address 352 WORTHINGTON ST

Time: 6:00 AM ☒ PM

% Gas / Air readily perceptible .03%

Recheck: ☒ YES ☐ NO

Instrument Used:

Make BACHBRACH

Model —

Serial # H21025

CODE OF MASSACHUSETTS REGULATIONS, 101.06 (20), STATES THAT A READING OF .15% OR LESS GAS IN AIR IS READILY PERCEPTIBLE TO THE NORMAL OR AVERAGE OLFACTORY SENSES.

EXHIBIT 12

Repairs at 453 Worthington Street, March 12, 2007

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
SECOND SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: January 4, 2013

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-2-25: Refer to CMA response to IR PL 1-24. Ticket 175395102 (3/6/2007), comments note: "found .30% gas at wall called for street stan" and "service has been re-run 000.00% LEL." Provide a detailed explanation regarding CMA's activities on this date, including actions taken to address the conditions found and actions taken to eliminate the hazard.

Response: The work order (WO-175395102) (3/6/2007) submitted in response to IR-PL-1-24, was for a meter change-out on a periodic test interval. The meter technician discovered and reported a gas reading at the basement wall where he was working. The comment "service has been re-run" is not accurate. Attachment IR-PL-2-25 contains the WOMS Distribution order (WO-6497409) which was issued that same day for a distribution crew repair. On March 6, 2007, the distribution crew responded to 453 Worthington and made a temporary repair to make it safe. That same crew returned on March 12, 2007, to seal the leaking joint as noted on the WO-6497409. Attachment IR-PL-2-25, pages 3 and 4 of 4 contain copies of the distribution crew worksheets.



Distribution Work Order

Project LD.

Identification:

At House	To House	Street Name	Location Phone	Work Order #
453	0	WORTHINGTON ST		6497409-1
Bldg. #	Unit #	Apt. #	Suite #	Town
				SPRINGFIELD
At Lot	To Lot	At Pole	To Pole	At Intersection
Kit and Grid #	To Intersection	Customer Account #	Initiated Date	Initiated Time
			03/06/2007	11:57
Customer Name	Entered By	CCS Number	Source	Source Name
		0-0-0	EMPLOYEE	ZIEMBA DAVID M
		Digging Conditions		

Work:

Work Code	Work Description	Estimated Units	Scheduled Date
LE8X JCIX	SERVICE - LEAK REPAIR	1	03/06/2007
		Leak Priority	Employee Assigned
		CLASS 1	TROLIO, NICOLA
		Cause of Leak	BSG Crew Assigned
		Job Safe #	TRUCK 386
		Job Priority	Contr. Crew Assigned

Outgoing Comments

CHECK FOR 910

Pipe Data:

	New Pipe	Exposed Pipe	Retired Pipe
Pipe Size		8"	
Pipe Type		CI	
Coat Type		LP	
Pressure			
Length			
Cut	S M L		S M L
Depth		40"	
Year		1930	
Pipe Cond.	LN - F - P - VP	LN - F - P - VP	LN - F - P - VP
Coat Cond.	G - MD - ED	G - MD - ED	G - MD - ED
Pit Depth			
# of Fits			
Fit Size			
Rate Class			

Other Data:

Anode Inst.	<input type="checkbox"/>
Flow Limiter Installed	<input type="checkbox"/>
Flow Limiter Tagged	<input type="checkbox"/>
Curb Cock Installed	<input type="checkbox"/>
Meter Barrier Installed	<input type="checkbox"/>
Meter Fit Installed	<input type="checkbox"/>
Inside	<input type="checkbox"/>
Outside	<input type="checkbox"/>
Soap Test	<input checked="" type="checkbox"/>
Pressure Test	<input type="checkbox"/>
Pounds/Square Inch	
Elpsd. PSI Time	
Patch Size Length	
Width	

Restoration Needed ☐

Restoration Done ☐

Bill to Customer? ☐

Sketch:

B. 453

→ 29 FT JOINT

Line of Main

Materials Used

1-8" QUICK KIT

Restoration Data:

	Required	Done	Date Done
Sand	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>
Gravel	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>
Base Coat	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>
Cold Patch	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>
Hot Patch	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>
Flow Fill	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>
Infra-Red	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>
Concrete	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>
Loam & Seed	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>
Other	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>
Size	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>		
Signature	<div style="width: 100%; height: 15px; background-color: #ccc;"></div>		

Permit Data:

Dig Safe:

Ticket #

Date Effective

Notification: _____

Permit Required:

Town ☐
 State ☐

Date Sent

Date Rec'd

Permit #

Water Notification: ☐ Date Called _____

Sewer Notification: ☐ Date Called _____

Stamps:

Completion Data:

Comments:

Completed Date

Date Started

Completed Units

Signature

Name

TFL-0010

DEFO RGE

Vehicle #

386

Total Hours Worked 9

Job	Arrive	Depart	Work Description		Complete ?
	:	:			
	:	:			
	:	:			
	:	:			
	:	:			
	:	:			
	:	:			
	:	:			
	:	:			
Lunch	:	:			

SUPERVISOR APPROVAL

Distribution department Daily Crew Sheet

Columbia Gas of Massachusetts
re: 453 Worthington St, Springfield, MA (11-23-12)
Attachment IR-PL-2-25
Page 4 of 4

Date Vehicle #
3-6-07 386

Empl #	Name
386	TILLO
1086	DEFORCE

Job	Work Order Number	Street #	Street Name	Town Code	Job Time	Pay Rate
	6467118-1	49	LYMAN ST	SH	2	1
	6497166	49	TOLCATT ST	SP	1	i
	6467118-1	49	LYMAN ST	SH	1	1
	6490409	453	WORTHINGTON ST	SP	1/2	1 1/2
	"	453	WORTHINGTON ST	SP	2	1
	6448595	50	COLLEGE ST	SH	2	1

Total Hours Worked 8 1/2

Daily Work Comments

Job	Arrive	Depart	Work Description	Complete ?
	:	:		
	:	:		
	:	:		
	:	:		
	:	:		
	:	:		
	:	:		
	:	:		
	:	:		
Lunch	:	:		

SUPERVISOR APPROVAL

[Signature]

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
SECOND SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: January 4, 2013

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-2-26: Refer to CMA response to IR PL 1-25. Provide a summary list noting the purpose of the CMA site visit at 453 Worthington Street, regarding: (a) leak history, (b) atmospheric inspections, (c) maintenance work on customer piping or equipment and Company owned piping. Provide the associated records for the itemized activities on the list.

Response:

- (a) CMA has not had any visits to 453 Worthington Street, Springfield, due to leaks during the period 2007 through November 22, 2012.
- (b) Inside atmospheric inspections were performed on June 27, 2008 and August 23, 2012. See Attachment IR-PL-1-25, pages 11 and 12 of 12.
- (c) Please see the following work orders ("WO") for information regarding maintenance on customer and Company piping and equipment:
 - Attachment IR-PL-2-26 (a) - WO for meter change out 3/6/2007.
 - Attachment IR-PL-2-26 (b) - WO for service call on poor pressure 3/17/2008.
 - Attachment IR-PL-2-26 (c) - WO for fitter to change out service regulator 3/17/2008.

Attachment  

Meter Work QuickView

File Create View Search Process Reports Security Admin Degree-Days Menu Help



Ticket# 175395102
WO # 6496863

Status: Complete in Field
Add WO Info

Work Order# 274

Charge Type: No Charge
Pipe Condition: Not Applicable

Special Pairs: H/W Pairs: Bill Amt: N/A

Account Information

Account # 124214003 S/S # 466741
Customer: B. S. C. Realty Inc.
Address: 453 Worthington St
Springfield MA 01105-1707
Hazard:

Appointment

Tech: Ryan Chis
Appt Window: 8:00 AM-11:59 AM
Scheduled: 03/08/2007
Priority: 7
Completed: 03/06/2007
Key #

- ☐ Call Ahead
- ☐ Auto
- ☐ Repeat
- ☐ Key

Meter Information

Old Meter # F47100 Size: AC250
New Meter # J51548 Size: AC250

Appliances (6)

Range: 00 Water Heater: 00 Dryer: 00
Boiler/Hr: 02 Space Heater: 00 Pool Heater: 00
Other:

Compass: ☒ Office ☐ Field ☐ Tech

Status History

GO TO 50 W/DEBRA PT WITH GO TO 91
TAYLOR 151

Date	Status	Time	Assigned To
03/05/2007	Initiated in CSIS	7:13 PM?	
03/05/2007	Scheduled	7:13 PM?	
03/05/2007	Assign	3:24 PM	Ryan Ch
03/06/2007	On route	11:29 AM	Ryan Ch
03/08/2007	On site	11:29 AM	Ryan Ch

Meter Work QuickView

File Create View Search Process Reports Security Admin Degree-Days Menu Help



Token# 175895102 Status Complete in Field Work Code 27A Charge Type No Charge
WCH# 6496658 Add WCH Info Pipe Condition Not Applicable

Special Pkg RTW Info Bill Amt N/A

Account Information

Account# 124214083 SIB# 468741
Customer B. S. C. Realty Inc.
Address 453 Worthington St.
Springfield MA 01105-1207
Hazard

Appointment
Tech Ryan Chris
Appt Window 8:00 AM-11:59 AM
Scheduled 03/06/2007
Priority 7
Completed 03/06/2007
Repeat
☐ Call Ahead
☐ Appt
☐ Repeat
☐ Key

Meter Information

Old Meter # E47100 Size AC250
New Meter # J51548 Size AC250

Appliances/ht
Range 00 Water Heater 00 Geyser 00
Boiler 02 Space Heater 00 Fuel Heater 00
Other

Comments Office Field Tech


Status History

ptmb lic EAT 029842741 on-site at 11:00 waited
over 20 min for customer to meet me found 30%
gas at wall called for street stan

Date	Status	Time	Assigned
03/05/2007	Initiated in CSIS	7:13 PM?	
03/05/2007	Scheduled	7:13 AM?	
03/05/2007	Assign	8:24 PM	Ryan Ch
03/06/2007	On route	11:29 AM	Ryan Ch
03/06/2007	On site	11:29 AM	Ryan Ch

Meter Work QuickView

File Create View Search Process Reports Security Admin Degree Days Menu Help


 Meter # 125495102
 WO # 6496653

 Status Complete in Field
 Add WO Info

Work Code 274

 Charge Type No Charge
 Pipe Condition Not Applicable

Special Pkts RTW Info Bill Amt N/A

Account Information

 Account # 124214003 SIS # 466741
 Customer B. S. G. Realty Inc.
 Address 453 Worthington St
 Springfield MA 01105-1707
 Hazard

Appointment

 Tech Ryan Chrls
 App Window 8:00 AM - 11:59 AM
 Scheduled 03/06/2007
 Priority 7
 Completed 03/06/2007
 Key

☐ PCH/Preced
☐ Sth
☐ Recd
☐ Key

Meter Information

 Old Meter # E47100 Size AC250
 New Meter # J51548 Size AC250

Appliances Lit

 Range 00 Water Heater 00
 House Htr 02 Space Heater 00
 Other Pool Heater 00

Comments Office File

service has been re-run 000.00% LEL

Status History

Date	Status	Time	Assigned
03/05/2007	Initiated in CSIS	7:13 PM?	
03/05/2007	Scheduled	7:13 PM?	
03/05/2007	Assign	8:24 PM	Ryan Chrls
03/06/2007	On route	11:29 AM	Ryan Chrls
03/06/2007	On site	11:29 AM	Ryan Chrls

Service Order QuickView

File Create View Search Process Reports **Service** Admin Dequeue-Data Menu Help



Ticket# 336017105 Work Order 300 **POOR PRESSURE** Charge Type: No Charge
WO# 8818700 Status: Complete in Field Service Plan (None)

Checkin Date: 03/17/2008 Add WO Info Special Falls SWF Info Bill Amt: N/A
Appliance Information Appliance: Not Applicable

Account # 124214003 S: H: O
Customer B. S. C. Realty Inc.
Address 453 Worthington St
Springfield MA 01105-1707
Hazard

Appliance
Tech Labier Mill
App Window 4:00 PM - 7:59 PM
Scheduled 03/17/2008
Priority 1
Completed 03/17/2008 KeyH
☐ CSIS Head
☐ Walk
☐ Repeat
☐ Key

Appliance Information

Appliance	
Make	Model
Serial	Serial

Parts Used

Part	Desc

Comments ☒ Office ☐ Field ☐ Tech

Status History

EST REPORTS PLD SATING ON PRESSURE
REGULATOR 413-244-2491 SWBT 10/2/00&M

Date	Status	Time	Assign
03/17/2008	Initiated in CSIS	5:27 PM	?
03/17/2008	Scheduled	5:27 PM	?
03/17/2008	Assign	6:27 PM	Labier
03/17/2008	Dispatched	6:27 PM	Labier

Service Order QuickView

File Create New Search Process Reports Security Admin Logout Days Menu Help



Ticket# 338017106 Work Code 300 P008 PRESSURE Change Type No Charge
 Work 6813700 Status Complete in Field Service Plan (None)

Created Date 03/17/2008 05:15:48 Sub Job Info Special Parts R/W/F Info Bill Amt N/A
 Account Information Pipe Condition Not Applicable

Account# 124214003 SIC# 0
 Customer B. S. C. Realty Inc.
 Address 453 Worthington St.
 Springfield MA 01105-1707
 Hazards
 Appointment
 Tech Labron Mill
 App Window 4:00 PM - 7:59 PM
 Scheduled 03/17/2008
 Priority 1
 Completed 03/17/2008
 Key#

Appliance Information
 Appliance
 Make Model
 Serial Serial#
 Parts Used
 Part# Desc

Comments ☐ Office ☒ Field ☐ Tech
 INSTALL NREW REG WITH PIPE
 Status History

Date	Status	Time	Assign
03/17/2008	Initiated in CSIS	5:27 PM	?
03/17/2008	Scheduled	5:27 PM	?
03/17/2008	Assign	6:27 PM	Labier
03/17/2008	Dispatched	6:27 PM	Labier



Checkplate No.	076 004 051548	Add Weight	Special Pairs	P/W	105	Oil	4m	N/A
Additional Information	Fire Location: Not Applicable							

Tech Labrier Hill ☒ Call Ahead
 Appointment Window: 4:00 PM - 7:59 PM ☐ Auto
 Scheduled: 03/17/2008 ☐ Repeat
 Priority: 1 ☐ Zip
 Completed: 03/17/2008 ☐ Note

● 同治十三年(1874) 日本出兵臺灣

圖書集成

Appliance	
Make	Model
Serial	Serial#

ESTR	DEMO
[Redacted Content]	[Redacted Content]

SEARCHED INDEXED

[illegible]

0000000000

Date	Status	Time	Assigned
03/17/2008	Initiated in CSIS	5:27 PM	?
03/17/2008	Scheduled	5:27 PM	?
03/17/2008	Assign	6:27 PM	Labier
03/17/2008	Dispatched	6:27 PM	Labier

Service Order QuickView

File Create View Search Process Reports Security Admin Devices Data Menu Help



Order #: 342507106 Work Code: 758 INSTALL SEAVY REG Charge Type: No Charge
 Work: 8813727 Status: Complete in Field Service Plan: (None)

Est. Bill Date: Orig Mtrk: 051848 Andk Wt: 6 Special Parts RTWP Info: Bill Amt: N/A
 Account Information: Pipe Condition: Fail

Account #: 124214003 SIC #: 486741
 Customer: B. S. L. Realty Inc.
 Address: 453 Worthington St
 Springfield MA 01105-1707
 Hazard:

Appointments:
 Tech: Sears Gregory T
 Appt Window: 8:00 AM - 7:59 PM
 Scheduled: 03/17/2008
 Priority: 5
 Completed: 03/17/2008 Keyit:
☐ Call/Show
☐ Add
☐ Report
☐ Key

Appliance Information

Appliance:

Make: Model:

Series: Serial:

Parts Used

Part #	Desc

Comments: ☒ Office ☐ Field ☐ Tech

REG 2538 - REG NO GOOD - GO INTO CLUB
 418 FR KEY - mlt waiting

Status History

Date	Status	Time	Assign
03/17/2008	Initiated in CSIS	7:30 PM	?
03/17/2008	Scheduled	7:30 PM	?
03/17/2008	Assign	7:37 PM	Sears
03/17/2008	Dispatched	7:37 PM	Sears

Service Order QuickView

File Create View Search Process Reports Security Admin Degree-Days Menu Help



Ticket# 342507106 Work Code: 755 **INSTALL SERV REG** Chemotype: No Charge
 WDI# 6819727 Status: Complete in Field Service Plan: (None)

Checkid Date: Original# 061648 Add WDI Info: Special Fats: Bl W F Info: Bill Amt: N/A
 Account Information: Fine Condition: Fair

Account #: 124214003 SIC #: 466741
 Customer: B. B. C. Realty Inc.
 Address: 453 Worthington St
 Springfield MA 01105-1707
 Hazard:

Appointment:
 Tech: Sears Gregory I
 Appl Window: 8:00 AM - 7:59 PM
 Scheduled: 03/17/2008
 Priority: 5
 Completed: 03/17/2008 Key:

☐ Call Ahead
☐ Auto
☐ Repeat
☐ Key

Appliance Information

Appliance	Make	Model	Serial

Parts Used

Part#	Desc

Comments: ☐ Office ☒ Field ☐ Tech

REPLACE REG RELITE APPL

Status History

Date	Status	Time	Assign
03/17/2008	Initiated in CSIS	7:30 PM	?
03/17/2008	Scheduled	7:30 PM	?
03/17/2008	Assign	7:37 PM	Sears
03/17/2008	Dispatched	7:37 PM	Sears

Service Order QuickView

File Create View Search Process Reports Security Admin Degree Days Menu Help



Order# 342507106 Work Code 756 INSTALL SERV REG Charge Type No Charge
WDR 6813727 Status Complete In Field Service Plan (None)

Checkin Date: 03/17/2008 05:16:48 Add Wdr Info: Special Pkts: P/W Info: Bill Amt: N/A
Appoint Information: Pipe Condition: Fair

Account# 124214003 812 8 466741
Customer B. S. D. Healy Inc.
Address 453 Worthington St
Springfield MA 01105-1707
Hazard

Appointment:
Tech: Sears Gregory I
Appt Window: 8:00 AM - 7:59 PM
Scheduled: 03/17/2008
Priority: 5
Completed: 03/17/2008 Key#

Appliance Information

Appliance:
Make: Model:
Serial: Serial#:

Parts Used

Part#	Desc

Comments: ☐ DMS ☐ FMS ☒ Tech

000.00% LEL

Status History

Date	Status	Time	Assigne
03/17/2008	Initiated in CSIS	7:30 PM	?
03/17/2008	Scheduled	7:30 PM	?
03/17/2008	Assign	7:37 PM	Sears
03/17/2008	Dispatched	7:37 PM	Sears

EXHIBIT 13

Leak Survey and Atmospheric Corrosion Inspection
453 Worthington Street

Dennis Henriques CMA Piping Inspection

Last Name	First Name	Middle Init
BSC REALTY INC		
Address 453 WORTHINGTON ST		
City : SPRINGFIELD	State : MA	Zip Code 01105
Phone # 4137882100	Extension :	
Site Id : 345323004		
Meter Loc CELLAR - FRONT		
Inspection Date 8-23-12	Inspection Activity	
Meter # : 051548	Comment :	
Leak Test : <input checked="" type="checkbox"/> Pass	<input type="checkbox"/> Fail	
Corrosion : <input checked="" type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Poor

- INSIDE PIPE
INSPECTION

Thursday, August 23, 2012

E364
Page 3 of 10

CMS Work Order

File Search Reports Menu Admin

CMS Work Order

CMS WOH#: 727382
Due Date: 12/15/2007
Compliance: 12/05/2006
Test: Inside Pipe Svy
Last Status: Initiated
Status Date: 03/12/2007

Type: Service
Id#: 466741

Detail Technicians

Technician
Premier Utility Locating

05:17

OK

Task Details

Task#	Test Date	Status
1	07/27/2006	Not Tested
2	12/15/2006	Not Tested
3	06/27/2008	Passed

Status Date:
Reason:
Action:
Travel Time:
Tech Minutes:
Woms W/Os:

Steps Comments Results Techs

CMS - INSIDE PIPE SURVEY

EXHIBIT 14

Leakage Survey Records – Worthington Street

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
FIRST SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: December 10, 2012

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-1-17: Provide the dates of the main and service leakage surveys the Operator performed on Worthington Street, between Spring and Dwight Streets, from January 1, 2007, to November 22, 2012, and the results of these surveys.

Response: Please see:

- Attachment IR-PL-1-22-Map-Winter Survey
- Attachment IR-PL-1-22-Map-Walking Survey
- Attachment IR-PL-1-22-Map-Mobile Survey.

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
FIRST SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)


Date: December 10, 2012

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-1-22: Provide records of the main servicing 453 Worthington Street, Springfield, between Spring and Chestnut Streets, including but not limited to, installation date, MAOP, operating pressure, leak history, and maintenance work, from January 1, 2007 to November 22, 2012.

Response: Please see Attachment IR-PL-1-22 for copies of the requested records. Please also see the following maps:

- Attachment IR-PL-1-22-Map-Winter Survey
- Attachment IR-PL-1-22-Map-Walking Survey
- Attachment IR-PL-1-22-Map-Mobile Survey.



SPRINGFIELD GAS LIGHT COMPANY


SCALE IN FEET

34

2013	Water	Pressure	Survey	Color
1	1-2-3-4	1-2-3-4	1-2-3-4	Yellow
2	5-6-7-8	5-6-7-8	5-6-7-8	Orange
3	9-10-11-12	9-10-11-12	9-10-11-12	Red
4	13-14-15-16	13-14-15-16	13-14-15-16	Purple
5	17-18-19-20	17-18-19-20	17-18-19-20	Blue
6	21-22-23-24	21-22-23-24	21-22-23-24	Green
7	25-26-27-28	25-26-27-28	25-26-27-28	Brown
8	29-30-31-32	29-30-31-32	29-30-31-32	Black
9	33-34-35-36	33-34-35-36	33-34-35-36	Grey
10	37-38-39-40	37-38-39-40	37-38-39-40	White
11	41-42-43-44	41-42-43-44	41-42-43-44	Light Blue

2013 Water Pressure Survey
Blue = Not Surveyed
DO NOT SURVEY

BUSINESS DISTRICT
MAY 24



2007 BUSINESS DISTRICT SURVEY		COUNCIL	
Ward	District	City	County
1	1	1	1
2	2	2	2
3	3	3	3
4	4	4	4
5	5	5	5
6	6	6	6
7	7	7	7
8	8	8	8
9	9	9	9
10	10	10	10
11	11	11	11
12	12	12	12
13	13	13	13
14	14	14	14
15	15	15	15
16	16	16	16
17	17	17	17
18	18	18	18
19	19	19	19
20	20	20	20
21	21	21	21
22	22	22	22
23	23	23	23
24	24	24	24
25	25	25	25
26	26	26	26
27	27	27	27
28	28	28	28
29	29	29	29
30	30	30	30
31	31	31	31
32	32	32	32
33	33	33	33
34	34	34	34
35	35	35	35
36	36	36	36
37	37	37	37
38	38	38	38
39	39	39	39
40	40	40	40
41	41	41	41
42	42	42	42
43	43	43	43
44	44	44	44
45	45	45	45
46	46	46	46
47	47	47	47
48	48	48	48
49	49	49	49
50	50	50	50
51	51	51	51
52	52	52	52
53	53	53	53
54	54	54	54
55	55	55	55
56	56	56	56
57	57	57	57
58	58	58	58
59	59	59	59
60	60	60	60
61	61	61	61
62	62	62	62
63	63	63	63
64	64	64	64
65	65	65	65
66	66	66	66
67	67	67	67
68	68	68	68
69	69	69	69
70	70	70	70
71	71	71	71
72	72	72	72
73	73	73	73
74	74	74	74
75	75	75	75
76	76	76	76
77	77	77	77
78	78	78	78
79	79	79	79
80	80	80	80
81	81	81	81
82	82	82	82
83	83	83	83
84	84	84	84
85	85	85	85
86	86	86	86
87	87	87	87
88	88	88	88
89	89	89	89
90	90	90	90
91	91	91	91
92	92	92	92
93	93	93	93
94	94	94	94
95	95	95	95
96	96	96	96
97	97	97	97
98	98	98	98
99	99	99	99
100	100	100	100

Completed Map By Ben/K.D.
Date 5/14/07
Little FC 6/7/20

2007 Walking Survey

- includes the following parts:
 - Springfield 16, 23, 34, 35, 40, 41
 - Longmeadow 1, 4, 5, 6, 15, 16
 - East Longmeadow 6, 7, 8, 13, 14, 15, 24, 25, 26
 - West Springfield 20, 21, 22, 23, 25, 36, 37, 38, 39, 40, 51, 55
 - Palmer 46, 47, 131, 132, 133, 134, 135, 136, 137, 138, 139, 141, 142, 143, 144, 145
 - South Hadley 66, 67A, 67, 68, 69, 70, 75, 76, 77, 78, 87
 - Granby 64, 65, 66, 70, 71, 72, 73, 74, 75, 76, 79, 80

[illegible]

2007 WALKING SURVEY


NO.	NAME	DATE	REMARKS
1	1st	1-1-1911	1st
2	2nd	2-1-1911	2nd
3	3rd	3-1-1911	3rd
4	4th	4-1-1911	4th
5	5th	5-1-1911	5th
6	6th	6-1-1911	6th
7	7th	7-1-1911	7th
8	8th	8-1-1911	8th
9	9th	9-1-1911	9th
10	10th	10-1-1911	10th
11	11th	11-1-1911	11th
12	12th	12-1-1911	12th
13	13th	13-1-1911	13th
14	14th	14-1-1911	14th
15	15th	15-1-1911	15th
16	16th	16-1-1911	16th
17	17th	17-1-1911	17th
18	18th	18-1-1911	18th
19	19th	19-1-1911	19th
20	20th	20-1-1911	20th
21	21st	21-1-1911	21st
22	22nd	22-1-1911	22nd
23	23rd	23-1-1911	23rd
24	24th	24-1-1911	24th
25	25th	25-1-1911	25th
26	26th	26-1-1911	26th
27	27th	27-1-1911	27th
28	28th	28-1-1911	28th
29	29th	29-1-1911	29th
30	30th	30-1-1911	30th
31	31st	31-1-1911	31st
32	32nd	32-1-1911	32nd
33	33rd	33-1-1911	33rd
34	34th	34-1-1911	34th
35	35th	35-1-1911	35th
36	36th	36-1-1911	36th
37	37th	37-1-1911	37th
38	38th	38-1-1911	38th
39	39th	39-1-1911	39th
40	40th	40-1-1911	40th
41	41st	41-1-1911	41st
42	42nd	42-1-1911	42nd
43	43rd	43-1-1911	43rd
44	44th	44-1-1911	44th
45	45th	45-1-1911	45th
46	46th	46-1-1911	46th
47	47th	47-1-1911	47th
48	48th	48-1-1911	48th
49	49th	49-1-1911	49th
50	50th	50-1-1911	50th
51	51st	51-1-1911	51st
52	52nd	52-1-1911	52nd
53	53rd	53-1-1911	53rd
54	54th	54-1-1911	54th
55	55th	55-1-1911	55th
56	56th	56-1-1911	56th
57	57th	57-1-1911	57th
58	58th	58-1-1911	58th
59	59th	59-1-1911	59th
60	60th	60-1-1911	60th
61	61st	61-1-1911	61st
62	62nd	62-1-1911	62nd
63	63rd	63-1-1911	63rd
64	64th	64-1-1911	64th
65	65th	65-1-1911	65th
66	66th	66-1-1911	66th
67	67th	67-1-1911	67th
68	68th	68-1-1911	68th
69	69th	69-1-1911	69th
70	70th	70-1-1911	70th
71	71st	71-1-1911	71st
72	72nd	72-1-1911	72nd
73	73rd	73-1-1911	73rd
74	74th	74-1-1911	74th
75	75th	75-1-1911	75th
76	76th	76-1-1911	76th
77	77th	77-1-1911	77th
78	78th	78-1-1911	78th
79	79th	79-1-1911	79th
80	80th	80-1-1911	80th
81	81st	81-1-1911	81st
82	82nd	82-1-1911	82nd
83	83rd	83-1-1911	83rd
84	84th	84-1-1911	84th
85	85th	85-1-1911	85th
86	86th	86-1-1911	86th
87	87th	87-1-1911	87th
88	88th	88-1-1911	88th
89	89th	89-1-1911	89th
90	90th	90-1-1911	90th
91	91st	91-1-1911	91st
92	92nd	92-1-1911	92nd
93	93rd	93-1-1911	93rd
94	94th	94-1-1911	94th
95	95th	95-1-1911	95th
96	96th	96-1-1911	96th
97	97th	97-1-1911	97th
98	98th	98-1-1911	98th
99	99th	99-1-1911	99th
100	100th	100-1-1911	100th

MOBILE SURVEY
MYLAR 34

SURVEYED ON
BUSINESS DISTRICT
SURVEY



SPRINGFIELD GAS LIGHT COMPANY



2011 Winter Patrol
Blue = Not Cast Iron
Do Not Survey



COL-EAST INC. LOW PRESSURE
MASON & PITFIELD

SPRINGFIELD GAS LIGHT COMPANY

SCALE IN FEET

34

NO.	NAME	DATE
1	SPRINGFIELD	1/1/11
2	SPRINGFIELD	1/1/11
3	SPRINGFIELD	1/1/11
4	SPRINGFIELD	1/1/11
5	SPRINGFIELD	1/1/11
6	SPRINGFIELD	1/1/11
7	SPRINGFIELD	1/1/11
8	SPRINGFIELD	1/1/11
9	SPRINGFIELD	1/1/11
10	SPRINGFIELD	1/1/11
11	SPRINGFIELD	1/1/11
12	SPRINGFIELD	1/1/11
13	SPRINGFIELD	1/1/11
14	SPRINGFIELD	1/1/11
15	SPRINGFIELD	1/1/11
16	SPRINGFIELD	1/1/11
17	SPRINGFIELD	1/1/11
18	SPRINGFIELD	1/1/11
19	SPRINGFIELD	1/1/11
20	SPRINGFIELD	1/1/11
21	SPRINGFIELD	1/1/11
22	SPRINGFIELD	1/1/11
23	SPRINGFIELD	1/1/11
24	SPRINGFIELD	1/1/11
25	SPRINGFIELD	1/1/11
26	SPRINGFIELD	1/1/11
27	SPRINGFIELD	1/1/11
28	SPRINGFIELD	1/1/11
29	SPRINGFIELD	1/1/11
30	SPRINGFIELD	1/1/11
31	SPRINGFIELD	1/1/11
32	SPRINGFIELD	1/1/11
33	SPRINGFIELD	1/1/11
34	SPRINGFIELD	1/1/11


2011 Leak Survey
MOBILE
Springfield
Mylar 34

SURVEYED ON
BUSINESS DISTRICT
SURVEY

NO.	NAME	DATE
1	W. J.
2	W. J.
3	W. J.
4	W. J.
5	W. J.
6	W. J.
7	W. J.
8	W. J.
9	W. J.
10	W. J.
11	W. J.
12	W. J.
13	W. J.
14	W. J.
15	W. J.

SURVEYED ON
 BUSINESS DISTRICT
 SURVEY
 MOBILE SURVEY
 MYLAR 34





SPRINGFIELD GAS LIGHT COMPANY

SCALE IN FEET

34

2010 LOCAL SURVEY

STREET	WALKING
1	100
2	100
3	100
4	100
5	100
6	100
7	100
8	100
9	100
10	100
11	100
12	100
13	100
14	100
15	100
16	100
17	100
18	100
19	100
20	100
21	100
22	100
23	100
24	100
25	100
26	100
27	100
28	100
29	100
30	100
31	100
32	100
33	100
34	100
35	100
36	100
37	100
38	100
39	100
40	100
41	100
42	100
43	100
44	100
45	100
46	100
47	100
48	100
49	100
50	100

2010 LOCAL SURVEY

STREET	WALKING
1	100
2	100
3	100
4	100
5	100
6	100
7	100
8	100
9	100
10	100
11	100
12	100
13	100
14	100
15	100
16	100
17	100
18	100
19	100
20	100
21	100
22	100
23	100
24	100
25	100
26	100
27	100
28	100
29	100
30	100
31	100
32	100
33	100
34	100
35	100
36	100
37	100
38	100
39	100
40	100
41	100
42	100
43	100
44	100
45	100
46	100
47	100
48	100
49	100
50	100

2010 LOCAL SURVEY

STREET	WALKING
1	100
2	100
3	100
4	100
5	100
6	100
7	100
8	100
9	100
10	100
11	100
12	100
13	100
14	100
15	100
16	100
17	100
18	100
19	100
20	100
21	100
22	100
23	100
24	100
25	100
26	100
27	100
28	100
29	100
30	100
31	100
32	100
33	100
34	100
35	100
36	100
37	100
38	100
39	100
40	100
41	100
42	100
43	100
44	100
45	100
46	100
47	100
48	100
49	100
50	100

2010 LOCAL SURVEY

STREET	WALKING
1	100
2	100
3	100
4	100
5	100
6	100
7	100
8	100
9	100
10	100
11	100
12	100
13	100
14	100
15	100
16	100
17	100
18	100
19	100
20	100
21	100
22	100
23	100
24	100
25	100
26	100
27	100
28	100
29	100
30	100
31	100
32	100
33	100
34	100
35	100
36	100
37	100
38	100
39	100
40	100
41	100
42	100
43	100
44	100
45	100
46	100
47	100
48	100
49	100
50	100

2010 LOCAL SURVEY

STREET	WALKING
1	100
2	100
3	100
4	100
5	100
6	100
7	100
8	100
9	100
10	100
11	100
12	100
13	100
14	100
15	100
16	100
17	100
18	100
19	100
20	100
21	100
22	100
23	100
24	100
25	100
26	100
27	100
28	100
29	100
30	100
31	100
32	100
33	100
34	100
35	100
36	100
37	100
38	100
39	100
40	100
41	100
42	100
43	100
44	100
45	100
46	100
47	100
48	100
49	100
50	100

2010 LOCAL SURVEY

STREET	WALKING
1	100
2	100
3	100
4	100
5	100
6	100
7	100
8	100
9	100
10	100
11	100
12	100
13	100
14	100
15	100
16	100
17	100
18	100
19	100
20	100
21	100
22	100
23	100
24	100
25	100
26	100
27	100
28	100
29	100
30	100
31	100
32	100
33	100
34	100
35	100
36	100
37	100
38	100
39	100
40	100
41	100
42	100
43	100
44	100
45	100
46	100
47	100
48	100
49	100
50	100

EXHIBIT 15

Post Incident Leakage Survey Results

COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF PUBLIC UTILITIES

RESPONSE OF COLUMBIA GAS OF MASSACHUSETTS TO THE
FIRST SET OF INFORMATION REQUESTS FROM THE D.P.U.
PIPELINE ENGINEERING AND SAFETY DIVISION

453 Worthington St., Springfield, MA (11-23-12)

Date: December 10, 2012

Responsible: Danny G. Cote, V.P. Pipeline Safety Compliance

IR-PL-1-19: Provide the results of the leak investigation the Operator performed after the Incident in the area surrounding Worthington Street. Provide a map of the area checked, and associated leak investigation documents.

Response: Please see Attachment IR-PL-1-19 (a) for the leak results.

Please see Attachment IR-PL-1-19 (b) for the map indicating the survey area.

Please see Attachment IR-PL-1-19 (c) for the map indicating the leak survey area and barhole readings.

7 pm - 7 am

Eric Shepard
#125884

11/25 - 11/26

Worthington / Scores

9:30 74%

11pm 74%

12:45am 52%

2:30am 52%

4:15am 52%

5:30am 72%



November 30, 2012



Survey Area in the Location of Worthington St
Springfield, MA